

VILLAGE OF METAMORA					
DESCRIPTION	MUTCD	SIZE (IN)	QUANTITY	72000100	72000200
				AREA - TY 1 (SQ.FT)	AREA - TY 2 (SQ.FT)
STOP	R1-1	30X30	166	1037.50	
YIELD	R1-2	36X36X36	18	70.13	
ALL WAY (PLAQUE)	R1-3P	18X06	45	33.75	
SPEED LIMIT 20	R2-1	24X30	1	5.00	
SPEED LIMIT 30	R2-1	24X30	11	55.00	
DO NOT ENTER	R5-1	30X30	2	12.50	
WRONG WAY	R5-1A	36X24	1	6.00	
WEIGHT LIMIT 4 TONS	R12-1	24X30	2	10.00	
SCHOOL SPEED LIMIT	S4-1100	24X48	6	48.00	
END SCHOOL ZONE	S5-2	24X30	1	5.00	
CURVE RIGHT	W1-2R	30X30	1	6.25	
TWO DIRECTION LARGE ARROW	W1-7	48X24	3	24.00	
STOP AHEAD (SYMBOL)	W3-1	30X30	4	25.00	
REDUCED SPEED LIMIT AHEAD 30 MPH	W3-5	36X36	4	36.00	
TRAFFIC FROM RIGHT DOES NOT STOP	W4-4aP	24X12	2	4.00	
TRAFFIC FROM LEFT DOES NOT STOP	W4-4aP	24X12	2	4.00	
ONCOMING TRAFFIC DOES NOT STOP	W4-4bP	24X12	2	4.00	
BIKE SYMBOL (FYG)	W11-1	30X30	1	6.25	
DEAD END	W14-1	30X30	4	25.00	
DOWNWARD DIAGONAL ARROW LEFT (FYG)	W16-7P	24X12	1	2.00	
		<b>TOTAL</b>	<b>277</b>	<b>1419.4</b>	<b>0.0</b>

PAY ITEM NUMBER	DESCRIPTION	UNIT	SIZE (FT)	QUANTITY	QUANTITY
					277
X7240195	REMOVE EXISTING SIGN PANEL	EACH			
Z0051398	REMOVE EXISTING SIGN POST	EACH			4
72800100	2"X2" TELESCOPING STEEL SIGN SUPPORT	FOOT	12	4	48
73100100	2.25"X2.25" TELESCOPING STEEL SIGN BASE	EACH			4
	ASSEMBLY FOR TELESCOPING POST <sub>1</sub>	EACH			252
72900100	METAL POST, TY A	FOOT	12	0	0
72900200	METAL POST, TY B	FOOT	12	0	0
	ASSEMBLY FOR METAL POST <sub>1</sub>	EACH			4
X7300105	WOOD SUPPORT, 4' X 4'	FOOT	12	0	0
X7300105	WOOD SUPPORT, 4' X 6'	FOOT	12	0	0
	ASSEMBLY FOR WOOD POST <sub>1</sub>	EACH			24
X7350010	SIGN SUPPORT BRACKET	EACH			3

(FYG) = FLUORESCENT YELLOW GREEN BACKGROUND COLOR  
 Note: FYG is only to be used in school zone areas.  
 1. Incidental items. See special provisions.

CITY OF MINONK					
DESCRIPTION	MUTCD	SIZE (IN)	NO. OF PIECES	72000100	72000200
				AREA - TY 1 (SQ.FT)	AREA - TY 2 (SQ.FT)
OBJECT MARKER TYPE 3, LEFT	OM3-L	12X36	1	3.00	
OBJECT MARKER TYPE 3, RIGHT	OM3-R	12X36	1	3.00	
STOP	R1-1	30X30	172	1075.00	
YIELD	R1-2	36X36X36	22	85.71	
ALL WAY (PLAQUE)	R1-3P	18X06	77	57.75	
SPEED LIMIT 20	R2-1	24X30	19	95.00	
SPEED LIMIT 25	R2-1	24X30	12	60.00	
SPEED LIMIT 30	R2-1	24X30	3	15.00	
SPEED LIMIT 35	R2-1	24X30	1	5.00	
CITYWIDE (PLAQUE)	R2-5aP	24X06	9	9.00	
UNLESS OTHERWISE POSTED (PLAQUE)	R2-5P	24X18	9	27.00	
NO U TURN	R3-4	24X24	5	20.00	
DO NOT ENTER	R5-1	30X30	2	12.50	
SCHOOL	S1-1	30X30	25	156.25	
SCHOOL SPEED LIMIT	S4-1100	24X48	13	104.00	
CURVE LEFT	W1-2L	30X30	1	6.25	
TWO DIRECTION LARGE ARROW	W1-7	48X24	3	24.00	
CROSS TRAFFIC DOES NOT STOP	W4-1100	30X18	4	15.00	
BUMP	W8-1	30X30	2	12.50	
FIRE TRUCK (SYMBOL)	W11-8	30X30	2	12.50	
ADVISORY SPEED (PLAQUE) 35 MPH	W13-1P	18X18	1	2.25	
DEAD END	W14-1	30X30	9	56.25	
		<b>TOTAL</b>	<b>393</b>	<b>1857.0</b>	<b>0.0</b>

PAY ITEM NUMBER	DESCRIPTION	UNIT	SIZE (FT)	NO. OF PIECES	QUANTITY
					395
X7240195	REMOVE EXISTING SIGN PANEL	EACH			
Z0051398	REMOVE EXISTING SIGN POST	EACH			9
72800100	2"X2" TELESCOPING STEEL SIGN SUPPORT	FOOT	12	9	108
73100100	2.25"X2.25" TELESCOPING STEEL SIGN BASE	EACH			9
	ASSEMBLY FOR TELESCOPING POST <sub>1</sub>	EACH			156
72900100	METAL POST, TY A	FOOT	12	0	0
72900200	METAL POST, TY B	FOOT	12	0	0
	ASSEMBLY FOR METAL POST <sub>1</sub>	EACH			200
X7300105	WOOD SUPPORT, 4' X 4'	FOOT	12	0	0
X7300105	WOOD SUPPORT, 4' X 6'	FOOT	12	0	0
	ASSEMBLY FOR WOOD POST <sub>1</sub>	EACH			41
X7350010	SIGN SUPPORT BRACKET	EACH			2

1. Incidental items. See special provisions.

VILLAGE OF PANOLA					
DESCRIPTION	MUTCD	SIZE	NO. OF PIECES	72000100	72000200
				AREA - TY 1 (SQ.FT)	AREA - TY 2 (SQ.FT)
SPEED LIMIT 20	R2-1	18X24	1	3.00	
REVERSE CURVE LEFT	W1-4L	30X30	2	12.50	
		<b>TOTAL</b>	<b>3</b>	<b>15.5</b>	<b>0.0</b>

PAY ITEM NUMBER	DESCRIPTION	UNIT	SIZE (FT)	NO. OF PIECES	QUANTITY
					3
X7240195	REMOVE EXISTING SIGN PANEL	EACH			
Z0051398	REMOVE EXISTING SIGN POST	EACH			0
72800100	2"X2" TELESCOPING STEEL SIGN SUPPORT	FOOT	12	0	0
73100100	2.25"X2.25" TELESCOPING STEEL SIGN BASE	EACH			0
	ASSEMBLY FOR TELESCOPING POST <sub>1</sub>	EACH			0
72900100	METAL POST, TY A	FOOT	12	0	0
72900200	METAL POST, TY B	FOOT	12	0	0
	ASSEMBLY FOR METAL POST <sub>1</sub>	EACH			0
X7300105	WOOD SUPPORT, 4' X 4'	FOOT	12	0	0
X7300105	WOOD SUPPORT, 4' X 6'	FOOT	12	0	0
	ASSEMBLY FOR WOOD POST <sub>1</sub>	EACH			3
X7350010	SIGN SUPPORT BRACKET	EACH			0

1. Incidental items. See special provisions.

DESIGNED - KK	REVISED - KK 01/30/2013
DRAWN - KK	REVISED -
CHECKED - BHI	REVISED -
DATE - 12/19/12	REVISED -

Woodford County  
Highway Department

Municipal Schedule

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	10-00016-00-50	Woodford	18	16
CONTRACT NO. 189628				

SCALE: SHEET NO. 16 OF 18 SHEETS STA. TO STA.