

VILLAGE OF WASHBURN					
DESCRIPTION	MUTCD	SIZE (IN)	NO. OF PIECES	72000100	72000200
				AREA - TY 1 (SQ. FT)	AREA - TY 2 (SQ. FT)
STOP	R1-1	30X30	72	450.00	
YIELD	R1-2	36X36X36	4	15.58	
ALL WAY (PLAQUE)	R1-3P	18X06	31	23.25	
SPEED LIMIT 5	R2-1	24X30	2	10.00	
SPEED LIMIT 25	R2-1	24X30	14	70.00	
WEIGHT LIMIT 5 TONS	R12-1	24X30	2	10.00	
SCHOOL	S1-1	30X30	2	12.50	
SCHOOL SPEED LIMIT	S4-1100	24X48	3	24.00	
DEAD END	W14-1	30X30	3	18.75	
		TOTAL	133	634.1	0.0

PAY ITEM NUMBER	DESCRIPTION	UNIT	SIZE (FT)	NO. OF PIECES	QUANTITY
X7240195	REMOVE EXISTING SIGN PANEL	EACH			133
Z0051398	REMOVE EXISTING SIGN POST	EACH			10
72800100	2"X2" TELESCOPING STEEL SIGN SUPPORT	FOOT	12	10	120
73100100	2.25"X2.25" TELESCOPING STEEL SIGN BASE	EACH			10
	ASSEMBLY FOR TELESCOPING POST,	EACH			12
72900100	METAL POST, TY A	FOOT	12	0	0
72900200	METAL POST, TY B	FOOT	12	0	0
	ASSEMBLY FOR METAL POST,	EACH			118
X7300105	WOOD SUPPORT, 4' X 4'	FOOT	12	0	0
X7300105	WOOD SUPPORT, 4' X 6'	FOOT	12	0	0
	ASSEMBLY FOR WOOD POST,	EACH			3
X7350010	SIGN SUPPORT BRACKET	EACH			0

1. Incidental items. See special provisions.

DESIGNED	KK	REVISED	KK 01/30/2013
DRAWN	KK	REVISED	
CHECKED	BWI	REVISED	
DATE	10/18/12	REVISED	

Woodford County
Highway Department

Municipal Schedule

SCALE: SHEET NO. 18 OF 18 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	10-00016-00-SG	Woodford	18	18
			CONTRACT NO.: 89628	