ILLINOIS ENVIRONMENTAL PROTECTION AGENCY



1021 NORTH GRAND AVENUE EAST, P.O. BOX 19276, SPRINGFIELD, ILLINOIS 62794-9276 • (217) 782-3397 BRUCE RAUNER, GOVERNOR ALEC MESSINA, DIRECTOR

217/782-3362

DEC 1 3 2018

Rock Island District Corps of Engineers Post Office Box 2004 Clock Tower Building Rock Island, IL 61204-2004

United States Coast Guard 1222 Spruce Street St. Louis, MO 63103-2832





Re: Illinois Department of Transportation – District 4 (Peoria and Tazewell Counties) East Bound US 150 Bridge – Illinois River, Unnamed Tributaries and Unnamed Wetlands Log # C-0081-17 [CoE appl. # 2018-443; Coast Guard# D8 DWB-884]

Gentlemen:

This Agency received a request on March 29, 2018 from the Illinois Department of Transportation – District 4 requesting necessary comments concerning the replacement of the bridge carrying Eastbound U.S. 150 over the Illinois River (McClugage Bridge) impacting the Illinois River, unnamed tributaries and unnamed wetlands. We offer the following comments.

Based on the information included in this submittal, it is our engineering judgment that the proposed project may be completed without causing water pollution as defined in the Illinois Environmental Protection Act, provided the project is carefully planned and supervised.

These comments are directed at the effect on water quality of the construction procedures involved in the above described project and are <u>not</u> an approval of any discharge resulting from the completed facility, nor an approval of the design of the facility. These comments do <u>not</u> supplant any permit responsibilities of the applicant toward the Agency.

This Agency hereby issues certification under Section 401 of the Clean Water Act (PL 95-217), subject to the applicant's compliance with the following conditions:

- 1. The applicant shall not cause:
 - a. violation of applicable water quality standards of the Illinois Pollution Control Board, Title 35, Subtitle C: Water Pollution Rules and Regulations;
 - b. water pollution defined and prohibited by the Illinois Environmental Protection Act;
 - c. violation of applicable provisions of the Illinois Environmental Protection Act; or
 - d. interference with water use practices near public recreation areas or water supply intakes.
- 2. The applicant shall provide adequate planning and supervision during the project construction period for implementing construction methods, processes and cleanup procedures necessary to prevent water pollution and control erosion.

- 3. Any spoil material excavated, dredged or otherwise produced must not be returned to the waterway but must be deposited in a self-contained area in compliance with all state statutes, regulations and permit requirements with no discharge to waters of the State unless a permit has been issued by this Agency. Any backfilling must be done with clean material and placed in a manner to prevent violation of applicable water quality standards.
- 4. All areas affected by construction shall be mulched and seeded as soon after construction as possible. The applicant shall undertake necessary measures and procedures to reduce erosion during construction. Interim measures to prevent erosion during construction shall be taken and may include the installation of staked straw bales, sedimentation basins and temporary mulching. All construction within the waterway shall be constructed during zero or low flow conditions. The applicant shall be responsible for obtaining an NPDES Storm Water Permit prior to initiating construction if the construction activity associated with the project will result in the disturbance of 1 (one) or more acres, total land area. An NPDES Storm Water Permit may be obtained by submitting a properly completed Notice of Intent (NOI) form by certified mail to the Agency's Division of Water Pollution Control, Permit Section.
- 5. The applicant shall implement erosion control measures consistent with the "Illinois Urban Manual" (IEPA/USDA, NRCS; 2017).
- 6. The proposed work shall be constructed with adequate erosion control measures (i.e., silt fences, straw bales, etc.) to prevent transport of sediment and materials to the adjoining wetlands and downstream.
- 7. Asphalt, bituminous material and concrete with protruding material such as reinforcing bar or mesh shall not be 1) used for backfill, 2) placed on shorelines/streambanks, or 3) placed in waters of the State.
- 8. The mitigation plan received by the Agency in July 12, 2018 and September 6, 2018 emails entitled "2018-443: McClugage Bridge" shall be implemented. Modifications to the mitigation plan must be submitted to the Agency for approval. The permittee shall submit annual reports by July 1 of each calendar year on the status of the mitigation. The first annual report shall include a hydric soils determination that represents the soils at the completion of initial construction for the wetland mitigation site(s). The permittee shall monitor the mitigation for 5 years after the completion of initial construction. A final report shall be submitted within 90 days after completion of a 5-year monitoring period. Each annual report and the final report shall include the following: IEPA Log No., date of completion of initial construction, representative photographs, updated topographic maps, description of work in the past year, the performance standards for the mitigation as stated in the mitigation plan, and the activities remaining to complete the mitigation plan. For wetland mitigation sites containing non-hydric soils at the time of initial construction, the final report shall include a hydric soils determination that represents the soils at the end of the 5-year monitoring period. For mitigation provided by purchase of mitigation banking credits, in lieu of the above monitoring and reporting, the permittee shall submit written proof from the mitigation bank that the mitigation credits have been purchased within thirty (30) days of said purchase. The subject reports and proof of purchase of mitigation credits shall be submitted to:

Illinois Environmental Protection Agency Bureau of Water Permit Section 1021 North Grand Avenue East Post Office Box 19276 Springfield, Illinois 62794-9276 Page No. 3 Log # C-0081-17

This certification becomes effective when the Department of the Army, Corps of Engineers and the U.S. Coast Guard includes the above conditions #1 through #8 as conditions of the requested permit issued pursuant to Section 404 of PL 95-217 and the General Bridge Act of 1946.

This certification does not grant immunity from any enforcement action found necessary by this Agency to meet its responsibilities in prevention, abatement, and control of water pollution.

Sincerely,

Darin E. LeCrone, P.E. Manager, Industrial Unit, Permit Section Division of Water Pollution Control

DEL:TJF:0081-17.docx

IEPA, Records Unit
IEPA, DWPC, FOS, Peoria
IDNR, Springfield
USEPA, Region 5
Mr. Nicholas Jack, Illinois Department of Transportation - District 4, 401 Main Street, Peoria, IL 61602-1111
Mr. Jeffrey Bushur, Hanson Professional Services, 1525 South Sixth Street, Springfield, IL 62703