



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 17, 2019

SUBJECT: Route MUN 3073 & FAU 1689 (Woodfield Road)
Section 14-00114-01-PV (Schaumburg)
Cook County
Contract No. 61F09
Item 159
April 26, 2019 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised pages 3-9 of the Special Provisions

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

Jack A. Elston, P.E.
Bureau Chief
Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E.", with a small "P.E." to the right.

By: Ted B. Walschleger, P.E.
Engineer of Project Management

“The Length of Holiday Period for Thanksgiving shall be from 5:00 AM the Wednesday prior to 11:59 PM the Sunday After”

Delete the fifth paragraph of Article 107.09 of the Standard Specifications:

“On weekends, excluding holidays, roadways with Average Daily Traffic of 25,000 or greater, all lanes shall be open to traffic from 3:00 P.M. Friday to midnight Sunday except where structure construction or major rehabilitation makes it impractical.”

MAINTENANCE OF ROADWAYS

Effective: September 30, 1985 Revised: November 1, 1996

Beginning on the date that work begins on this project, the Contractor shall assume responsibility for normal maintenance of all existing roadways within the limits of the improvement. This normal maintenance shall include all repair work deemed necessary by the Engineer, but shall not include snow removal operations. Traffic control and protection for maintenance of roadways will be provided by the Contractor as required by the Engineer.

If items of work have not been provided in the contract, or otherwise specified for payment, such items, including the accompanying traffic control and protection required by the Engineer, will be paid for in accordance with Article 109.04 of the “Standard Specifications”.

TOLLWAY PERMIT AND BOND

Effective: January 13, 1989

The Contractor will be required to obtain a permit from the Illinois State Toll Highway Authority (ISTHA) according to Article 107.04 of the Standard Specifications prior to initiating any lane closures on the Tollway or doing any work on the ISTHA right of way. As part of the permit, the Contractor will be required to post a surety bond with the ISTHA.

The Contractor will furnish a copy of the authorized permit to the Engineer.

STATUS OF UTILITIES (D-1)

Effective: June 1, 2016

Utility companies and/or municipal owners located within the construction limits of this project have provided the following information in regard to their facilities and the proposed improvements. The tables below contain a description of specific conflicts to be resolved and/or facilities which will require some action on the part of the Department’s contractor to proceed with work. Each table entry includes an identification of the action necessary and, if applicable, the estimated duration required for the resolution.

UTILITIES TO BE ADJUSTED

Conflicts noted below have been identified by following the suggested staging plan included in the contract. The company has been notified of all conflicts and will be required to obtain

the necessary permits to complete their work; in some instances resolution will be a function of the construction staging. The responsible agency must relocate or complete new installations as noted in the action column; this work has been deemed necessary to be complete for the Department's contractor to then work in the stage under which the item has been listed.

Pre-Stage

STAGE/ LOCATION	TYPE	DESCRIPTION	RESPONSIBLE AGENCY	ACTION
Woodfield Road – Sta. 129+36, 47' RT	Pedestal	Existing AT&T pedestal in conflict with proposed curb and gutter	AT&T	AT&T to relocate facilities <u>32</u> days
Woodfield Road – Sta. 129+35 – Sta. 136+04 LT	Existing Underground Duct	Existing AT&T duct in conflict with proposed drainage structures and signal equipment	AT&T	
Woodfield Road – Sta. 136+07 – Sta. 137+53 RT	Existing Underground Cable	Existing AT&T cable in conflict with proposed drainage structures	AT&T	
Woodfield Road – Sta. 131+00 RT – Sta. 132+35	Buried Fiber Optic line	Existing fiber optic line in conflict with drainage structures	MCI/Verizon	MCI/Verizon to lower and relocate lines <u>30</u> days
Woodfield Road – Sta. 133+50 RT- 136+23 RT	Buried Fiber Optic line	Existing fiber optic line in conflict with drainage structures	MCI/Verizon	
Woodfield Road - Sta. 122+50 to 137+36 (RT side) West Frontage Road – (RT side)	Underground gas main	Multiple conflicts with proposed drainage, signals, and lighting structures	Nicor	Nicor to relocate line <u>60</u> days
Woodfield Road – Sta. 137+35, 11' RT	Existing Buried Cable	Existing fiber optic cable in conflict with proposed detention sewer	Zayo	Zayo to relocate cable <u>5</u> days
West Frontage Road – Sta. 703+90, 52' LT	Underground Fiber Optic line	Existing fiber optic cable in conflict with drainage structure	Zayo	Zayo to relocate cable <u>5</u> days

Pre-Stage: 32 Days Total Installation for AT&T
Pre-Stage: 30 Days Total Installation for MCI/Verizon
Pre-Stage: 60 Days Total Installation for Nicor
Pre-Stage: 10 Days Total Installation for Zayo
Pre-Stage Total: 132 Days

Stage 1

STAGE/ LOCATION	TYPE	DESCRIPTION	OWNER	ACTION
Woodfield Road – 127+90, 49' RT	Adjust during construction	Adjust handhole to proposed grade	Vinakom	Vinakom to adjust <u>1</u> day
Woodfield Road – 137+24, 61' RT	Adjust during construction	Adjust handhole to proposed grade	Zayo	Zayo to adjust <u>1</u> day
Woodfield Road – 137+29, 54' RT	Adjust during construction	Adjust handhole to proposed grade	MCI/XO	MCI/Verizon to adjust <u>1</u> day
Woodfield Road – 137+55, 74' RT	Adjust during construction	Adjust handhole to proposed grade	ComEd	ComEd to adjust <u>1</u> day
West Frontage Road – 703+11, 52' LT	Adjust during construction	Adjust handhole to proposed grade	MCI/XO	MCI/Verizon to adjust <u>1</u> day

Stage 1: 1 Day Total Installation for Vinakom
Stage 1: 1 Day Total Installation for Zayo
Stage 1: 2 Days Total Installation for MCI/Verizon
Stage 1: 1 Day Total Installation for ComEd
Stage 1 Total: 5 Days

Stage 2

STAGE/ LOCATION	TYPE	DESCRIPTION	OWNER	ACTION
Woodfield Road – 123+68, 39' LT	Adjust during construction	Adjust handhole to proposed grade	ComEd	ComEd to adjust <u>1</u> day
Woodfield Road – 128+22, 36' LT	Adjust during construction	Adjust handhole to proposed grade	MCI/XO	MCI/Verizon to adjust <u>1</u> day
Woodfield Road – 129+35, 29' LT	Adjust during construction	Adjust handhole to proposed grade	AT&T	AT&T to adjust <u>1</u> day
Woodfield Road – 129+41, 39' LT	Adjust during construction	Adjust handhole to proposed grade	ComEd	ComEd to adjust <u>1</u> day

Stage 2: 2 Days Total Installation for ComEd
Stage 2: 1 Day Total Installation for MCI/Verizon
Stage 2: 1 Day Total Installation for AT&T
Stage 2 Total: 4 Days

Stage 3

No conflicts anticipated

The following contact information is what was used during the preparation of the plans as provided by the Agency/Company responsible for resolution of the conflict.

Agency/Comp any Responsible to Resolve Conflict	Name of contact	Address	Phone	e-mail address
AT&T	Bruce Robbins	1000 Commerce Drive, Floor 1, Oak Brook, IL 60523	630.573.6471	br1831@att.com
ComEd	Christian Mukania	1 Lincoln Center, 6 th Floor, Oakbrook Terrace, IL 60181	630.437.2927	Christian.Mukania@ comed.com

MCI / Verizon / XO	Mel Conn	1515 E. Woodfield Road, Schaumburg, IL 60173	847-706-2315	Mel.conn@verizon.com
NICOR	Bruce Koppang	1844 Ferry Road, Naperville, IL 60563	630.388.3046	bkoppan@southernco.com
Zayo	John Ferraresi		312.216.0450	John.ferraresi@zayo.com

UTILITIES TO BE WATCHED AND PROTECTED

The areas of concern noted below have been identified by following the suggested staging plan included for the contract. The information provided is not a comprehensive list of all remaining utilities, but those which during coordination were identified as ones which might require the Department's contractor to take into consideration when making the determination of the means and methods that would be required to construct the proposed improvement. In some instances the contractor will be responsible to notify the owner in advance of the work to take place so necessary staffing on the owners part can be secured.

Stage 1

STAGE/ LOCATION	TYPE	DESCRIPTION	OWNER	ACTION
Woodfield Road – 129+35 RT – 133+22 RT, 137+07 RT – 137+53 RT	Buried communication and fiber optic lines	Existing communication and fiber optic lines; exercise caution during excavation	AT&T	Contractor to call JULIE before excavation
Woodfield Road – 122+50 RT – 138+25 RT	Buried electric lines	Existing electric lines; exercise caution during excavation	ComEd	Contractor to call JULIE before excavation
Woodfield Road – 138+18, 12' RT	Buried electric duct	Existing 3'X2' electric duct crossing proposed 15" storm sewer – ComEd to brace duct prior to storm sewer installation	ComEd	Contractor to inform ComEd at least 4 weeks prior to beginning storm sewer work in the area
West Frontage Road (LT side)	Sanitary/combined sewer	Existing sanitary/combined sewer; exercise caution during excavation	MWRD	Contractor to call JULIE before excavation; manhole lids shall not be buried or covered. Facility shall be protected from damage by the Contractor during construction.

Martingale Road (RT side)	Buried fiber optic lines	Existing fiber optic lines; exercise caution during excavation	Vinakom	Contractor to call JULIE before excavation
Woodfield Road – 127+50 RT – 137+25 RT, Martingale Road (RT side)	Buried fiber optic lines	Existing fiber optic lines; exercise caution during excavation	Zayo	Contractor to call JULIE before excavation

Stage 2

STAGE/ LOCATION	TYPE	DESCRIPTION	OWNER	ACTION
Woodfield Road – 129+35 LT – 137+05 LT	Buried communication and fiber optic lines	Existing communication and fiber optic lines; exercise caution during excavation	AT&T	Contractor to call JULIE before excavation
Woodfield Road – 122+50 LT – 143+40 LT, East Frontage Road (right side)	Buried electric lines	Existing electric lines; exercise caution during excavation	ComEd	Contractor to call JULIE before excavation
Woodfield Road – 122+50 LT – 128+00 LT	Buried fiber optic lines	Existing fiber optic lines; exercise caution during excavation	Vinakom	Contractor to call JULIE before excavation

The following contact information is what was used during the preparation of the plans as provided by the Agency/Company responsible for resolution of the conflict.

Agency/Company Responsible to Resolve Conflict	Name of contact	Address	Phone	e-mail address
MWRD	Stephen Kaszonyi	111 East Erie, Chicago, IL 60611	312.751.3170	Kaszonysi@mwrdd.org
Vinakom	Dicky Patel	860 Remington Road, Schaumburg, IL 60173	847.592.5785	dicky.patel@vinakom.com
West Shore Pipeline	Bobby Lafan	12920 Bell Road, Lemont, IL 60439	630.257.7583	

The above represents the best information available to the Department and is included for the convenience of the bidder. The days required for conflict resolution should be taken into account in the bid as this information has also been factored into the timeline identified for the project when setting the completion date. The applicable portions of the Standard Specifications for Road and Bridge Construction shall apply.

Estimated duration of time provided in the action column for the first conflicts identified will begin on the date of the executed contract regardless of the status of the utility relocations. The responsible agencies will be working toward resolving subsequent conflicts in conjunction with contractor activities in the number of days noted.

The estimated relocation dates must be part of the progress schedule submitted by the contractor. A utility kickoff meeting will be scheduled between the Department, the Department's contractor and the utility companies. The Department's contractor is responsible for contacting J.U.L.I.E. prior to any and all excavation work.