



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 16, 2024

SUBJECT FAP Route 345 (US 20)  
Project NHPP-S0V8(143)  
Section FAP 345 23 Safety  
Kane County  
Contract No. 62U84  
Item No. 25, April 26, 2024 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices
2. Revised page iii of the Table of Contents to the Special Provisions
3. Added pages 183 & 184 to the Special Provisions
4. Revised sheets 14 of the Plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read "Jack A. Elston".

Jack A. Elston, P.E.  
Bureau Chief, Design and Environment

MTS

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE) ..... 159  
SEEDING (BDE) ..... 160  
SHORT TERM AND TEMPORARY PAVEMENT MARKINGS (BDE)..... 165  
SOURCE OF SUPPLY AND QUALITY REQUIREMENTS (BDE) ..... 168  
STEEL COST ADJUSTMENT (BDE)..... 168  
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE) ..... 172  
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) ..... 172  
SUBMISSION OF PAYROLL RECORDS (BDE) ..... 173  
TRAINING SPECIAL PROVISIONS (BDE) ..... 174  
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION..... 177  
VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE) ..... 179  
WEEKLY DBE TRUCKING REPORTS (BDE)..... 179  
WOOD SIGN SUPPORT (BDE)..... 179  
WORK ZONE TRAFFIC CONTROL DEVICES (BDE) ..... 180  
MENTOR-PROTÉGÉ PROGRAM ..... 182  
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC) ..... 183

## REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC)

**Description.** This work shall consist of the removal and disposal of regulated substances according to Section 669 of the Standard Specifications as revised below.

**Contract Specific Sites.** The excavated soil and groundwater within the areas listed below shall be managed as either “uncontaminated soil”, hazardous waste, special waste or non-special waste. For stationing, the lateral distance is measured from centerline and the farthest distance is the offset distance or construction limit, whichever is less.

**Soil Disposal Analysis.** When the waste material requires sampling for landfill disposal acceptance, the Contractor shall secure a written list of the specific analytical parameters and analytical methods required by the landfill. The Contractor shall collect and analyze the required number of samples for the parameters required by the landfill using the appropriate analytical procedures. A copy of the required parameters and analytical methods (from landfill email or on landfill letterhead) shall be provided as Attachment 4A of the BDE 2733 (Regulated Substances Final Construction Report). The price shall include all sampling materials and effort necessary for collection and management of the samples, including transportation of samples from the job site to the laboratory. The Contractor shall be responsible for determining the specific disposal facilities to be utilized; and collect and analyze any samples required for disposal facility acceptance using a NELAP certified analytical laboratory registered with the State of Illinois.

### Site 2773V2-4: Agricultural Land, 37W900-38W300 Blocks of US 20, Elgin, Kane County

- Station 142+50 to Station 143+30 (CL US 20), 0 to 65 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). Contaminants of concern sampling parameter: Manganese.

### 2773V2-10: TBK Bank, 3151 US 20, Elgin, Kane County

- Station 146+05 to Station 146+70 (CL US 20) 80 to 175 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). Contaminants of concern sampling parameter: Manganese.
- Station 146+25 to Station 147+20 (CL US 20) 0 to 80 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameter: Manganese.
- Station 147+20 to Station 148+05 (CL US 20) 0 to 55 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(3). Contaminants of concern sampling parameters: Benzo(a)pyrene and Manganese.

### Site 2773V2-13: The Galleria of Elgin, 3091 US 20, Elgin, Kane County

- Station 153+45 to Station 154+15 (CL US 20) 0 to 55 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(3). Contaminants of concern sampling parameter: Benzo(a)pyrene.
- Station 154+15 to Station 156+40 (CL US 20) 0 to 55 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Contaminants of concern sampling parameters: Arsenic and Benzo(a)pyrene.

Added 4/16/2024

Site 2773V2-23: Residences, 3000 Cranston Avenue and 3001-3021 Settlers Parkway, Elgin, Kane County

- Station 168+50 to Station 172+50 (CL US 20) 0 to 105 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters: Iron, Lead and Manganese.
- Station 172+50 to Station 174+50 (CL US 20) 0 to 70 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). Contaminants of concern sampling parameters: Iron and Manganese.

Site 2773V2-24: ROW, 3000 Block of Longcommon Parkway, Elgin, Kane County

- Station 179+85 to Station 181+10 (CL US 20) 0 to 125 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters: Lead and Manganese.
- Station 181+10 to Station 184+00 (CL US 20) 0 to 95 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). Contaminants of concern sampling parameter: Manganese.

Site 2773V2-26: Vacant Land, 3019-3020 Longcommon Parkway, Elgin, Kane County

- Station 184+00 to Station 185+10 (CL US 20) 0 to 95 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Contaminants of concern sampling parameter: Manganese.
- Station 185+10 to Station 186+20 (CL US 20) 0 to 95 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). Contaminants of concern sampling parameter: Manganese.

Site 2773V2-27: Residences and Vacant Lot, 2877-2881 Sarah Court, 106-130 Barnes Road, 2801-2809 Weld Road, 2769-2813 Randall Ridge Drive, 2651-2763 Colonial Drive, 2600 Block of Boxwood Drive and 2614-2644 Boxwood Drive, Elgin, Kane County

- Station 179+10 to Station 180+50 (CL US 20) 0 to 130 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). Contaminants of concern sampling parameter: Manganese.

Site 2773V2-28: Residences, 37W444-37386 Raleigh Court, 11N352-11N372 Williamsburg Drive, and 37W271 Weld Road, unincorporated Elgin, Kane County

- Station 186+20 to Station 187+60 (CL US 20) 0 to 95 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters: Iron and Manganese.

**Work Zones**

Three distinct OSHA HAZWOPER work zones (exclusion, decontamination, and support) shall apply to projects adjacent to or within sites with documented leaking underground storage tank (LUST) incidents, or sites under management in accordance with the requirements of the Site Remediation Program (SRP), Resource Conservation and Recovery Act (RCRA), or Comprehensive Environmental Response, Compensation and Liability Act (CERCLA), or as deemed necessary. For this project, the work zones apply for the following ISGS PESA Sites:

**None**

Added 4/16/2024