

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				80% FED 20% STATE BRIDGE 0010	051-0077
20200100	EARTH EXCAVATION	CU YD	80	80	
20300100	CHANNEL EXCAVATION	CU YD	722	722	
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	421	421	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	125	125	
28000400	PERIMETER EROSION BARRIER	FOOT	1,796	1,796	
28100109	STONE RIPRAP, CLASS A5	SQ YD	781	781	
28200200	FILTER FABRIC	SQ YD	682	682	
35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SQ YD	499	499	
40600295	POLYMERIZED BITUMINOUS MATERIALS (TACK COAT)	POUND	1,505	1,505	
40600990	TEMPORARY RAMP	SQ YD	312	312	
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	231	231	
40604164	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N90	TON	182	182	
42000080	PAVEMENT CONNECTOR (PCC) FOR BRIDGE APPROACH SLAB	SQ YD	120	120	
44000100	PAVEMENT REMOVAL	SQ YD	336	336	
44004250	PAVED SHOULDER REMOVAL	SQ YD	384	384	

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				80% FED 20% STATE BRIDGE 0010	051-0077
44201811	CLASS D PATCHES, TYPE I, 14 INCH	SQ YD	24	24	
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	263	263	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	19	19	
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	256	256	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	159	159	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1	
50200100	STRUCTURE EXCAVATION	CU YD	414	414	
50300225	CONCRETE STRUCTURES	CU YD	178.4	178.4	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	262.0	262.0	
50300260	BRIDGE DECK GROOVING	SQ YD	898	898	
50300300	PROTECTIVE COAT	SQ YD	1,146	1,146	
50301350	CONCRETE SUPERSTRUCTURE (APPROACH SLAB)	CU YD	105.9	105.9	
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1	1	
50500505	STUD SHEAR CONNECTORS	EACH	4,518	4,518	

* SPECIALTY ITEM
^ SPECIAL PROVISION

* SPECIALTY ITEM
^ SPECIAL PROVISION

△ REVISED 4-10-2024

MODEL: S00 (Sheet)
FILE NAME: P:\1\X5050X\31\X51\46 - IDOT P1B 200-034.D1 V1 Bartlett West\W0326-Tami\CAD\CADD_sheets\74443-phs-S00.dgn



USER NAME = kulrich	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 0.16666633' / in.	CHECKED -	REVISED -
PLOT DATE = 10/18/2023	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N/A SHEET 1 OF 3 SHEETS STA. ___+___ TO STA. ___+___

F.A.P. RTE. 327	SECTION (3,2B) B-1	COUNTY LAWRENCE	TOTAL SHEETS 54	SHEET NO. 3
CONTRACT NO. 74443				
ILLINOIS FED. AID PROJECT				