

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		POPE	16	2
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
IDNR PROJECT NO. 5-06-004				

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL
20100500	TREE REMOVAL, ACRES	ACRE	0.1
20200100	EARTH EXCAVATION	CU YD	2,826
20800150	TRENCH BACKFILL	CU YD	17
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	226
21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	50
● 25000100	SEEDING, CLASS 1	ACRE	0.5
● 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	45
● 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	45
● 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	45
● 25100115	MULCH, METHOD 2	ACRE	0.3
● 25100630	EROSION CONTROL BLANKET	SQ YD	1225
● 28000300	TEMPORARY DITCH CHECKS	EACH	6
28000400	PERIMETER EROSION BARRIER	FOOT	718
28000500	INLET AND PIPE PROTECTION	EACH	1
31101000	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	1,455
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	20
40300300	BITUMINOUS MATERIALS (COVER AND SEAL COATS)	GALLON	1,055
40300600	SEAL COAT AGGREGATE	TON	45
● 40300800	EMULSIFIED ASPHALT (FOG SEAL)	GALLON	3,115
● 42000110	PORTLAND CEMENT CONCRETE PAVEMENT 6 1/2"	SQ YD	6,100
48101200	AGGREGATE SHOULDERS, TYPE B	TON	65
● 50105220	PIPE CULVERT REMOVAL	FOOT	12
54201270	PIPE CULVERTS, TYPE 2, RCCP 15"	FOOT	54

CODE NO.	ITEM	UNIT	TOTAL
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1
67100100	MOBILIZATION	L SUM	1
● 70103700	TRAFFIC CONTROL COMPLETE	L SUM	1
● 78001100	PAINT PAVEMENT MARKING-LETTERS AND SYMBOLS	SQ FT	23
● 78001110	PAINT PAVEMENT MARKING-LINE 4"	FOOT	7,415
● 78001180	PAINT PAVEMENT MARKING- LINE 24"	FOOT	15
● 80400105	ELECTRIC SERVICE INSTALLATION, SPECIAL	EACH	1
● 81012300	CONDUIT IN TRENCH, 1" DIA., PVC	FOOT	1,631
● 81100300	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., GALVANIZED STEEL	FOOT	120
● 81300320	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 8" X 8" X 6"	EACH	6
● 81400730	HANDHOLE, COMPOSITE CONCRETE	EACH	3
● 81702120	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 8	FOOT	<b>5100</b>
● 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1,631
● 82105600	LUMINAIRE, SODIUM VAPOR, HIGH MAST, HORIZONTAL MOUNT, 400 WATT	EACH	6
● 82500505	LIGHTING CONTROLLER, SPECIAL	EACH	1
● 83057235	LIGHT POLE, WOOD, 40 FOOT, CLASS 5, WITH 15 FT MAST ARM	EACH	6
● 70013798	CONSTRUCTION LAYOUT	L SUM	1
● X0325727	WOOD POST (SPECIAL)	EACH	78
● A2006516	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	5
● A2002316	TREE, BETULA NIGRA (RIVER BIRCH), 2" CALIPER, BALLED AND BURLAPPED	EACH	5
XX004371	INLETS TYPE B TYPE 61 GRATE	EACH	1

● SPECIALTY ITEMS  
 \* SPECIAL PROVISION  
*Rev.*

REVISIONS	
DATE	NAME
03/20/07	JJ

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SUMMARY OF QUANTITIES  
 IDOT / IDNR  
 GOLCONDA MARINA RECREATION AREA

SCALE: VERT.  
 HORIZ.  
 DATE: 8/17/06

DRAWN BY: MAI  
 CHECKED BY: RGD