

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PARK ROADS	LAKE	26	2
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
IDNR PROJECT NO.	2-06-003	100%		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL	1000 100% STATE
20100500	TREE REMOVAL, ACRES	ACRE	0.9	
20200100	EARTH EXCAVATION	CU YD	7,865	
20800150	TRENCH BACKFILL	CU YD	18	
** 21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	1,272	
21400100	GRADING AND SHAPING DITCHES	FOOT	225	
25000110	SEEDING, CLASS 1A	ACRE	0.1	
** 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	9	
** 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	9	
** 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	9	
** * 25002014	SEEDING, CLASS 4A (MODIFIED)	ACRE	2.6	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	260	
28000300	TEMPORARY DITCH CHECKS	EACH	44	
28000400	PERIMETER EROSION BARRIER	FOOT	1,440	
28000500	INLET AND PIPE PROTECTION	EACH	5	
28100725	STONE DUMPED RIPRAP, CLASS B3	SO YD	2	
35100100	AGGREGATE BASE COURSE, TYPE A	TON	160	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	3,290	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	110	
40603100	HOT-MIX ASPHALT, BINDER COURSE, IL-19.0L, N30	TON	35	
40603305	HOT-MIX ASPHALT, SURFACE COURSE, MIX "C", N30	TON	30	
54200430	PIPE CULVERT, TYPE 1 RCCP, 15"	FOOT	95	
54200433	PIPE CULVERT, TYPE 1 RCCP, 18"	FOOT	122	
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	6	
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	3	
66500105	WOVEN WIRE FENCE, 4'	FOOT	1,445	

CODE NO.	ITEM	UNIT	TOTAL
67100100	MOBILIZATION	L SUM	1
* 70103700	TRAFFIC CONTROL COMPLETE	L SUM	1
** 72000100	SIGN PANEL-TYPE 1	SO FT	61
** 72000200	SIGN PANEL-TYPE 2	SO FT	10
** 73000100	WOOD SIGN SUPPORT	FOOT	154
** 78001180	PAINT PAVEMENT MARKING- LINE 24"	FOOT	15
* Z0013798	CONSTRUCTION LAYOUT	L SUM	1
** A2001016	TREE, ACER RUBRUM (RED MAPLE), 2" CALIPER, BALLED AND BURLAPPED	EACH	6
** A2002716	TREE, CARYA OVATA (SHAGBARK HICKORY), 2" CALIPER, BALLED AND BURLAPPED	EACH	6
** A2002916	TREE, CELTIS OCCIDENTIALIS (COMMON HACKBERRY), 2" CALIPER, BALLED AND BURLAPPED	EACH	7
** A2006416	TREE, QUERCUS ALBA (WHITE OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	17
** A2006516	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	15
** A2006716	TREE, QUERCUS MACROCARPA (BUR OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	17
** A2007150	TREE, QUERCUS VELUNTINA (BLACK OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	6
** A2007816	TREE, TILIA AMERICANA (AMERICAN LINDEN/BASSWOOD), 2" CALIPER, BALLED AND BURLAPPED	EACH	6
* XX004371	INLETS, TYPE B, TYPE 61 GRATE	EACH	1
** * XX006338	EROSION CONTROL BLANKET (SPECIAL)	SO YD	255
** * 25100106	MULCH (SPECIAL)	ACRE	2.6
* X0301797	GATE REMOVAL	EACH	1
* X0325724	GATE, SPECIAL 18"	EACH	1
* X0325725	GATE, SPECIAL 30'	EACH	1

* SPECIAL PROVISION
** SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
IDOT / IDNR
REDWING SLOUGH STATE NATURAL AREA

SCALE: VERT.
HORIZ.
DATE: 12/01/06

DRAWN BY: JJ
CHECKED BY: PJM