

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2742	2005-061 RS	COOK	28	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

**D-91-066-06**

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE								
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	1000	(PARKING) 50% STATE 50% VILLAGE Y025	PARKING 100% VILLAGE OF MAYWOOD Y025				CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	1000	(PARKING) 50% STATE 50% VILLAGE Y025	PARKING 100% VILLAGE OF MAYWOOD Y025			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	14	12	2					67100100	MOBILIZATION	L SUM	1	1					
40600300	AGGREGATE (PRIME COAT)	TON	65	57	8					70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	10	9	1					70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1						70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	510	510						70300100	SHORT-TERM PAVEMENT MARKING	FOOT	6000	6000					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	178	178						70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	300	300					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2825	2551	274					70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	600	600					
42001300	PROTECTIVE COAT	SQ YD	120	79		41				70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	200	200					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	32741	28189	4552					70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	450	450					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	535	300		235			* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	300	300						
44002224	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 6"	SQ YD	1065	1065					* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	15916	15916						
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	260	260					* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	600	600						
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	295	295					* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	200	200						
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	480	480					* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	700	700						
55039700	STORM SEWERS TO BE CLEANED	FOOT	50	50					* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	520	520						
60250200	CATCH BASINS TO BE ADJUSTED	EACH	4	4					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	520	520						
60251740	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	1	1					* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	735	735						
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	1	1					X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4						
60255500	MANHOLES TO BE ADJUSTED	EACH	1	1					X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	50	50						
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1					X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1415	1223	192					
60260100	INLETS TO BE ADJUSTED	EACH	2	2					Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	55	55						
60260200	INLETS TO BE ADJUSTED (SPECIAL)	EACH	1	1															
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	50	50															
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	8	8															
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	42	42															
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6															

\*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

Rev.