

SUMMARY OF QUANTITIES			100% STATE URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT		1000-2A			
20201006	GRADING AND SHAPING SHOULDERS	UNIT	210	210			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	22	22			
40600300	AGGREGATE (PRIME COAT)	TON	110	110			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	17	17			
40600895	CONSTRUCTING TEST STRIP	EACH	2	2			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	295	295			
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	92	92			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	4629	4629			
42001300	PROTECTIVE COAT	SQ YD	790	790			
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	53500	53500			
44000198	HOT-MIX ASPHALT SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	912	912			
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	3250	3250			
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	544	544			
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	52	52			
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	368	368			
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	45	45			
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	850	850			
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	145	145			
55039700	STORM SEWERS TO BE CLEANED	FOOT	3000	3000			
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	6	6			
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	14	14			
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	12	12			
60404940	FRAMES AND GRATES, TYPE 23	EACH	23	23			
60604300	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (VARIABLE WIDTH GUTTER FLAG)	FOOT	250	250			
63200310	GUARDRAIL REMOVAL	FOOT	37.5	37.5			
63200710	STEEL PLATE BEAM GUARD RAIL REMOVAL, TYPE A	FOOT	150	150			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6			

SUMMARY OF QUANTITIES			100% STATE URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT		1000-2A			
67100100	MOBILIZATION	L SUM	1	1			
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1			
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1			
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1			
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	16	16			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	14010	14010			
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	254.8	254.8			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	32976	32976			
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1248	1248			
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	753	753			
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	32	32			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	17358	17358			
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	254.8	254.8			
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	32976	32976			
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1248	1248			
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	753	753			
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	32	32			
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	410	410			
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	7	7			
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	1	1			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	371	371			
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	465	465			
X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	1500	1500			

\* SPECIALITY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**FAP 525: US 20 (GRANT HIGHWAY)  
 MEYER ROAD TO WEST UNION ROAD**  
**SUMMARY OF QUANTITIES**

Rev.