

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
525	(11 & 12) RS-II	MCHENRY	21	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		URBAN 1000 100% STATE				
20201006	GRADING AND SHAPING SHOULDERS	UNIT	650	650				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	42	42				
40600300	AGGREGATE (PRIME COAT)	TON	200	200				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	35	35				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	120	120				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	230	230				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	8355	8355				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	96510	96510				
44002215	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 3/4"	SQ YD	900	900				
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	745	745				
44201745	CLASS D PATCHES, TYPE III, 8 INCH	SQ YD	75	75				
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	60	60				
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	2600	2600				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	1				
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1				
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	64400	64400				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	73	73				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	112100	112100				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	500	500				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	850	850				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	105	105				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		URBAN 1000 100% STATE				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	19400	19400				
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	73	73				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	112110	112110				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	500	500				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	850	850				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	105	105				
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	773	773				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	713	713				
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4				
X406710T	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE IL-4.75, N50	TON	4180	4180				

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
US 20
SUMMARY OF QUANTITIES

Rev.

PLOT DATE: 2/10/2007

2/10/2007 9:58:00 AM C:\PROJECTS\60B64\60B64.DWG