CONTRACT NO. 64800

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	130BR-4	BOONE	147	6
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

	CODE NUMBER	ITEM	UNITS	TOTAL	80%-FED 20%-STATE I000 ROADWAY	80%-FED 20%-STATE X081-2A BRIDGE
	20100110	TREE REMOVAL (6 TO 15 UNITS)	UNIT	73	73	
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	42	42	
	20200100	EARTH EXCAVATION	CU. YD	13,852	13,852	
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU. YD	139	139	
	20300100	CHANNEL EXCAVATION	CU. YD	2382	2382	
	20400800	FURNISHED EXCAVATION	CU. YD	2588	2588	
	20600310	QUARRY RUN GRANULAR EMBANKMENT	CU. YD	3550	3550	
	20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU. YD	164		164
	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ. YD	11142	11142	
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ. YD	11960	11960	
	21301048	EXPLORATION TRENCH 48" DEPTH	FOOT	500	500	
*	25000210	SEEDING, CLASS 2A	ACRE	2.35	2.35	
*	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	404	404	
*	25000310	SEEDING, CLASS 4	ACRE	1.91	1.91	
*	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	404	404	
*	25000320	SEEDING, CLASS 5	ACRE	1.91	1.91	
*	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	404	404	
*	25000750	MOWING	ACRE	2.35	2.35	
*	25001010	SEEDING, CLASS 2 (MODIFIED)	ACRE	0.22	0.22	
*	25100115	MULCH, METHOD 2	ACRE	5.1	5.1	
	25100630	EROSION CONTROL BLANKET	SQ. YD.	9430	9430	
	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	2128	2128	
	28000300	TEMPORARY DITCH CHECKS	EACH	57	57	
	28000400	PERIMETER EROSION BARRIER	FOOT	1005	1005	
	28000500	INLET AND PIPE PROTECTION	EACH	3	3	
	28100107	STONE RIPRAP, CLASS A4	SQ. YD.	64	51	13
	28100109	STONE RIPRAP, CLASS A5	SQ. YD.	765		765
	28200200	FILTER FABRIC	SQ. YD.	842	64	778
	31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ. YD.	290	290	
	31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ. YD.	3932	3932	
	31100935	SUB-BASE GRANULAR MATERIAL, TYPE A 18"	SQ. YD.	6409	6409	
	31100965	SUB-BASE GRANULAR MATERIAL, TYPE A 24"	SQ. YD.	534	534	
	40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	253	253	
	40701851	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 8 1/2"	SQ. YD.	4404	4404	
	40701921	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 12"	SQ. YD.	3489	3489	
	42001165	BRIDGE APPROACH PAVEMENT	SQ. YD.	270		270

* SPECIALTY ITEM

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

SUMMARY OF QUANTITIES

PLOT DATE = Fri Dec 15 08:46:22 2006
FILE NAME = c:\pwworking\d03\d0302\sd0302sv-.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = dhilerso