

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	130BR-4	BOONE	147	14
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

28000250 TEMPORARY EROSION CONTROL SEEDING

POUND	LOCATION	TO	STAGE
1135	STA. 100+00	121+00	STAGE I - LT & RT (RUNAROUND)
993	STA. 428+00	450+00	STAGE II - LT - IL 173
2128	TOTAL		

28000300 TEMPORARY DITCH CHECKS

EACH	LOCATION	STAGE
1	STA. 101+00	20' LT
1	STA. 102+50	22.75' LT
1	STA. 104+00	27' LT
1	STA. 105+50	31.4' LT
1	STA. 107+00	35.6' LT
1	STA. 108+50	38' LT
1	STA. 110+00	42' LT
1	STA. 111+50	28' LT
1	STA. 112+25	35' LT
1	STA. 113+00	29' LT
1	STA. 113+75	26' LT
1	STA. 114+60	28' LT
1	STA. 116+00	29' LT
1	STA. 117+50	27' LT
1	STA. 119+00	25' LT
1	STA. 120+50	24' LT
1	STA. 108+00	27' RT
1	STA. 109+50	27' RT
1	STA. 111+00	28' RT
1	STA. 112+50	30' RT
1	STA. 114+00	30' RT
1	STA. 433+00	23' LT
1	STA. 433+00	31' RT
2	STA. 434+50	36' LT&RT
1	STA. 436+00	42' LT
1	STA. 436+00	39' RT
2	STA. 437+50	44' LT&RT
1	STA. 439+00	44' LT
1	STA. 439+00	47' RT
1	STA. 440+25	55' RT
1	STA. 440+50	40' LT
1	STA. 440+50	53' RT
1	STA. 441+25	49' RT
1	STA. 442+00	47' LT
1	STA. 442+00	45' RT
1	STA. 442+75	48' RT
1	STA. 443+50	43' LT
1	STA. 443+50	41' RT
1	STA. 445+00	35' LT
1	STA. 445+00	39' RT
1	STA. 446+50	22' LT
1	STA. 446+50	32' RT
1	STA. 432+00	27' LT
1	STA. 433+50	30' LT
1	STA. 436+50	55' LT
1	STA. 438+00	69' LT
1	STA. 438+75	69' LT
1	STA. 439+50	51' LT
1	STA. 440+50	44' LT
1	STA. 442+00	59' LT
1	STA. 443+50	52' LT
1	STA. 445+00	41' LT
1	STA. 446+50	35' LT
1	STA. 448+00	30' LT
1	STA. 449+50	28' LT
57	TOTAL	

28000400 PERIMETER EROSION BARRIER

FOOT	LOCATION	TO	STAGE
100	STA. 107+00	108+00	LT STAGE I - RUNAROUND
100	STA. 114+00	115+00	LT STAGE I - RUNAROUND
251	STA. 433+50	436+00	RT STAGE II - IL 173
103	STA. 439+50	440+50	RT STAGE II - IL 173
251	STA. 433+50	436+00	LT STAGE III - IL 173
200	STA. 443+00	445+00	LT STAGE III - IL 173
1005	TOTAL		

28000500 INLET & PIPE PROTECTION

EACH	LOCATION	STAGE
1	STA. 107+50	17' RT
1	STA. 111+85	38' LT
1	STA. 114+50	19' RT
3	TOTAL	

28100107 STONE RIPRAP, CLASS A4

SQ. YD.	LOCATION	SIZE	STAGE
3.3	STA. 107+50	5' x 6'	STAGE I - RUNAROUND
44.4	STA. 111+78	10' x 40'	STAGE I - RUNAROUND
3.3	STA. 114+50	5' x 6'	STAGE I - RUNAROUND
3.1	STA. 439+05	3.5' x 8'	STAGE II - RT
3.1	STA. 439+12.27	3.5' x 8'	STAGE III - LT
3.1	STA. 440+63.73	3.5' x 8'	STAGE II - RT
3.1	STA. 440+70.78	3.5' x 8'	STAGE III - LT
64	TOTAL		

28200200 FILTER FABRIC

SQ. YD.	LOCATION	SIZE	STAGE
3.3	STA. 107+50	5' x 6'	STAGE I - RUNAROUND
44.4	STA. 111+78	10' x 40'	STAGE I - RUNAROUND
3.3	STA. 114+50	5' x 6'	STAGE I - RUNAROUND
3.1	STA. 439+05	3.5' x 8'	STAGE II - RT
3.1	STA. 439+12.27	3.5' x 8'	STAGE III - LT
3.1	STA. 440+63.73	3.5' x 8'	STAGE II - RT
3.1	STA. 440+70.78	3.5' x 8'	STAGE III - LT
64	TOTAL		

42001430 BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)

SQ. YD.	LOCATION	TYPE	WIDTH
27.65	STA. 438+92.96	CENTERED	6' x 41.47'
27.65	STA. 440+83.04	CENTERED	6' x 41.47'
55.3	TOTAL		

44000100 PAVEMENT REMOVAL

SQ. YD.	LOCATION	TO	STAGE
5172.69	STA. 100+35.6	121+51.7	
1311.56	STA. 432+96	437+50	
193.21	STA. 438+85	439+51.88	
1432.89	STA. 442+00	446+96	
8110	TOTAL		

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
SCALE:	VERT. HORIZ.	DRAWN BY
DATE		CHECKED BY

PLOT DATE = Fri Feb 23 09:16:28 2007
 PLOT SCALE = 500000
 USER NAME = ditzleras