

| | | | | |
|---------------------|---------|---------------------------|--------------|-----------|
| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 30L | 2LT-1 | STEPHENSON | 64 | 12 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | | ILLINOIS FED. AID PROJECT | | |

SCHEDULE OF QUANTITIES

| | | | | |
|----------|---|-----------|--------------|------------------------------------|
| Z0028700 | GRANULAR SUBGRADE REPLACEMENT | | | |
| | CU YD | LOCATION | OFFSET | REMARKS |
| | 17 | 374+84.6 | | 26'x35' UNDER PATCH |
| | 12 | 385+50 | | 26'x25' UNDER PATCH |
| | 29 TOTAL | | | |
| Z0030250 | IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3 | | | |
| | EACH | LOCATION | OFFSET | REMARKS |
| | 1 | 373+47.3 | 4' RT | STAGE I |
| | 1 | 376+22 | 4' RT | STAGE I |
| | 2 TOTAL | | | |
| Z0030350 | IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3 | | | |
| | EACH | LOCATION | OFFSET | REMARKS |
| | 1 | 373+58.7 | 5.87' LT | STAGE II |
| | 1 | 376+22 | 5.35' LT | STAGE II |
| | 2 TOTAL | | | |
| Z0075300 | TIE BARS | | | |
| | EACH | LOCATION | OFFSET | REMARKS |
| | 18 | 374+67.12 | TO 375+02.12 | |
| XX004900 | TIRE REINFORCEMENT MAT | | | |
| | SQ. YD | LOCATION | OFFSET | REMARKS |
| | 333 | 374+84.6 | LT | 12' Streambed and 1:4 & Var Slopes |
| | 239 | 374+84.6 | RT | 12' Streambed and 1:4 & Var Slopes |
| | 572 TOTAL | | | |
| X0323988 | TEMPORARY SOIL RETENTION SYSTEM | | | |
| | SQ. FT | LOCATION | OFFSET | REMARKS |
| | 286 | 374+58.6 | TO 375+10.6 | |
| | 286 TOTAL | | | |

PLOT DATE = Tue Jan 16 10:56:28 2007
 FILE NAME = c:\projects\21105\11105.dgn
 PLOT SCALE = 50.0000 / 1
 REFERENCE = SHEET