

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
138	475-4	WINNEBAGO	7	2
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

# SUMMARY OF QUANTITIES

Y031-1F

PAY CODE	ITEM	UNIT	TOTAL
X0325335	CONDUIT INSTALLED, 1 1/2" DIA., NON-METALLIC	FOOT	12
67100100	MOBILIZATION	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
80500100	SERVICE INSTALLATION, TYPE A	EACH	1
81400100	HANDHOLE	EACH	5
81400300	DOUBLE HANDHOLE	EACH	1
81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP TYPE USE) 1/C NO. 10	FOOT	1528
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	4
82500605	LIGHTING CONTROLLER PHOTOCCELL RELAY	EACH	1
85000300	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	L SUM	1
85700300	FULL-ACTUATED CONTROLLER AND TYPE V CABINET	EACH	1
86200200	UNINTERRUPTIBLE POWER SUPPLY, STANDARD	EACH	1
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 5C	FOOT	2533
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 7C	FOOT	438
87301815	ELECTRIC CABLE IN CONDUIT, SERVICE, NO 6 3C	FOOT	32
87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 14 FT.	EACH	2
87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 16 FT.	EACH	1
87702850	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 24 FT.	EACH	1
87702860	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 26 FT.	EACH	1
87702980	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 50 FT.	EACH	2
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	9

Y031-1F  
90% FED  
5% STATE  
10% VILLAGE

87800150	CONCRETE FOUNDATION, TYPE C	FOOT	3
87800400	CONCRETE FOUNDATION, TYPE E, 30-INCH DIAMETER	FOOT	27
87800415	CONCRETE FOUNDATION, TYPE E, 36-INCH DIAMETER	FOOT	30
88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2
88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	7
88040120	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	2
88040150	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1
88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	1
88200400	TRAFFIC SIGNAL BACKPLATE, FORMED PLASTIC	EACH	10
X0323153	ELECTRIC CABLE IN CONDUIT, GROUND, NO. 6 1C (GREEN)	FOOT	537
X0324887	CONDUIT INSTALLED, 2 1/2" <sup>DIA.</sup> NON-METALLIC	FOOT	164
X0324888	CONDUIT INSTALLED, 4" <sup>DIA.</sup> NON-METALLIC	FOOT	539
X0962500	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	L SUM	1
X7240500	RELOCATE EXISTING SIGNS	EACH	10
* X7800500	POLYUREA PAVEMENT MARKING - LETTERS AND SYMBOLS, SPECIAL	SQ. FT	42
* X7800510	POLYUREA PAYMENT MARKING SPECIAL - LINE 4"	FOOT	409
* X7800580	POLYUREA PAVEMENT MARKING SPECIAL - LINE 24"	FOOT	38
XX002192	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, COMPLETE	EACH	1
XX003165	VIDEO CAMERA DETECTOR SYSTEM	EACH	1

\* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT.  
HORIZ.  
DATE

DRAWN BY  
CHECKED BY

## SUMMARY OF QUANTITIES

PLDT DATE = Wed Feb 07 09:20:01 2007  
FILE NAME = \\s22ar-2\users\hills\proj\proj\11\_251\_0 FOREST HILLS\Forest hills plan sheet.dgn  
USER NAME = hills