

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	(50-5,6)1-1	LASALLE	10	6
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

MAINLINE SCHEDULE

LOCATION STATION TO STATION	LENGTH	HOT-MIX ASPH. SURF. REM 3 1/2" SQ YD	HOT-MIX ASPH. SURF. REM SPECIAL SQ YD	POLY. HOT-MIX ASPH. SURF. MIX E N90 TON	POLY. HOT-MIX ASPH. BINDER IL-19.0 N90 TON	HOT-MIX ASPHALT SHOULDER TON	BIT MATL PR CT GAL	AGG PR CT TON	MIX FOR CR, JTS, & FLANGEWAYS TON	LEVEL BINDER (HM) TON
LASALLE COUNTY										
EASTBOUND DRIVING LANE										
671+45 TO 672+50	105	140		10	18		11.2	0.3	0.04	0.07
711+00 TO 720+00	900	1200		84	151		96.0	2.4	0.36	0.60
768+00 TO 795+00	2700	3600		252	453		288.0	7.2	1.08	1.80
823+00 TO 824+00	100	133		9	17		10.7	0.3	0.04	0.07
845+00 TO 855+00	1000	1333		93	168		106.7	2.7	0.40	0.67
882+50 TO 887+50	500	667		47	84		53.3	1.3	0.20	0.33
895+00 TO 905+00	1000	1333		93	168		106.7	2.7	0.40	0.67
937+50 TO 942+50	500	667		47	84		53.3	1.3	0.20	0.33
960+50 TO 962+50	200	267		19	34		21.3	0.5	0.08	0.13
991+50 TO 992+50	100	133		9	17		10.7	0.3	0.04	0.07
EASTBOUND PASSING LANE										
	563		125			14	10.0			
775+00 TO 784+00	900	1200		84	151		96.0	2.4	0.36	0.60
895+00 TO 905+00	1000	1333		93	168		106.7	2.7	0.40	0.67
WESTBOUND DRIVING LANE										
671+50 TO 696+50	2500	3333		233	420		266.7	6.7	1.00	1.66
730+00 TO 762+00	3200	4267		299	538		341.3	8.5	1.28	2.13
765+00 TO 766+00	100	133		10	17		10.7	0.3	0.04	0.07
769+00 TO 772+00	300	400		28	50		32.0	0.8	0.12	0.20
779+60 TO 780+50	90	120		9	15		9.6	0.2	0.04	0.06
785+00 TO 810+30	2530	3374		236	425		269.9	6.7	1.00	1.69
811+30 TO 838+00	2670	3560		249	448		284.8	7.1	1.07	1.78
907+50 TO 908+50	100	133		10	17		10.7	0.3	0.04	0.07
918+50 TO 922+00	350	467		33	59		37.3	0.9	0.14	0.23
937+05 TO 941+00	395	527		37	66		42.1	1.0	0.16	0.26
958+00 TO 961+50	350	467		33	59		37.3	0.9	0.14	0.23
969+00 TO 985+00	1600	2133		149	269		170.7	4.3	0.64	1.07
993+50 TO 997+50	400	533		37	67		42.7	1.1	0.16	0.27
1001+00 TO 1002+25	125	167		12	21		13.3	0.3	0.05	0.08
1003+25 TO 1008+00	475	633		44	80		50.7	1.3	0.19	0.32
1012+50 TO 1018+00	550	733		51	92		58.7	1.5	0.22	0.37
1060+00 TO 1061+00	100	133		9	17		10.7	0.3	0.04	0.07
1070+70 TO 1073+40	270	360		25	45		28.8	0.7	0.11	0.18
1074+00 TO 1085+50	1150	1533		107	193		122.7	3.1	0.46	0.77
1086+00 TO 1088+90	290	387		27	49		30.9	0.8	0.12	0.19
1147+50 TO 1152+50	500	667		47	84		53.3	1.3	0.20	0.33
1155+51 BK = 724+16 AH										
727+50 TO 731+50	400	533		37	67		42.7	1.1	0.16	0.27
WESTBOUND PASSING LANE										
	563		125			14	10.0			
937+05 TO 942+50	545	727		51	92		58.1	1.4	0.22	0.36
969+00 TO 985+00	1600	2133		149	269		170.6	4.3	0.64	1.07
1155+51 BK = 724+16 AH										
734+00 TO 735+00	100	133		9	17		10.7	0.3	0.04	0.07
TOTAL	30821	39592	250	2771	4989	28	3187.6	79.3	11.88	19.81