

# SUMMARY OF QUANTITIES

F. A. P. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
693	24 RADIUS IMPROV. OF	TAZEWELL		3
STA.	TO STA.			
FED. ROAD DIST. NO. 6	SLURRIES	FED. AID PROJECT		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	URBAN	CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT		100% STATE 1000				
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	552	552				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	134	134				
25100630	EROSION CONTROL BLANKET	SQ YD	134	134				
28000500	INLET AND PIPE PROTECTION	EACH	1	1				
31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	552	552				
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	484	484				
44000100	PAVEMENT REMOVAL	SQ YD	402	402				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	203	203				
60238500	INLETS, TYPE A, WITH SALVAGED FRAME AND GRATE	EACH	1	1				
60500060	REMOVING INLETS	EACH	1	1				
60605000	COMBINATION <sup>CONCRETE</sup> CURB AND GUTTER, TYPE B-6.24	FOOT	196.2	196.2				
67100100	MOBILIZATION	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	20	20				
70106301	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601, LOCATION 1	L SUM	1	1				
70106302	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601, LOCATION 2	L SUM	1	1				

\* SPECIALTY ITEMS