

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
693	04 RADIUS IMPROV. 2007	TAZEWELL		6
STA.		TO STA.		
FED. ROAD DIST. NO. 4		ILLINOIS	FED. AID PROJECT	

78005100 - EPOXY PAVEMENT MARKING - LETTERS & SYMBOLS	
LOCATION	SQ. FT.
MARGARET ST.	
RT. STA. 107+28 16.8'	15.6
RT. STA. 107+94 16.8'	15.6
TOTAL	31

Z0012750-CONCRETE MEDIAN REPAIR	
LOCATION	SQ FT
SECOND ST.	
RT. STA. 13+12	3
TOTAL	3

78005150 - EPOXY PAVEMENT MARKING - LINE 12"	
LOCATION	FOOT
ISLAND CHEVERONS AT 20' CENTERS	82
TOTAL	82

42000501 - PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	
LOCATION	SQ YD
107+93.8 MARGARET ST. TO 14+5.6 SECOND ST.	483.8
TOTAL	484

60605000 - COMB. CONC. CURB AND GUTTER, TYPE B-6.24	
LOCATION	FOOT
107+93.8 MARGARET ST. TO 14+5.6 SECOND ST.	196.2
TOTAL	196.2

X7015005 - CHANGEABLE MESSAGE SIGN	
LOCATION	CAL DAY
JOB SITE	45
TOTAL	45

31101400 - SUB-BASE GRANULAR MATERIAL, TYPE B 6"	
LOCATION	SQ YD
107+93.8 MARGARET ST. TO 14+5.6 SECOND ST.	551.3
TOTAL	552

78005140 - EPOXY PAVEMENT MARKING - LINE 8"	
LOCATION	FOOT
STA. 107+94 TO 108+66 (MARGARET ST.)	73.1
STA. 107+94 (MARGARET ST.) TO 14+06 (2ND ST.)	199.10
STA. 108+32 (MARGARET ST.) TO STA. 13+27 (2ND ST.)	152.80
STA. 13+25 TO 13+75 (2ND ST.)	47.90
TOTAL	473

67100100 - MOBILIZATION	
LOCATION	L SUM
JOB SITE	1
TOTAL	1

21001000 - GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	
LOCATION	SQ YD
107+93.8 MARGARET ST. TO 14+5.6 SECOND ST.	551.3
TOTAL	552

70103815 - TRAFFIC CONTROL SURVEILLANCE	
LOCATION	CAL DAY
JOB SITE	20
TOTAL	20

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. DATE  
HORIZ.

DRAWN BY  
CHECKED BY