

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57&74	*	**	151	17

* D5 CABLE GUARD 2007-2
 ** CHAMPAIGN, DEWITT & DOUGLAS

SCHEDULES OF QUANTITIES

25100630 EROSION CONTROL BLANKET

STATION (SQ. YD.)

DOUGLAS COUNTY

LOC #1 TUSCOLA (I-57 SBDL SHOULDER)

470+00	4.0
475+00	4.0
480+00	4.0
483+00	4.0
490+00	4.0
497+50	4.0
502+45	4.0

SUBTOTAL = 28.0

CHAMPAIGN COUNTY

LOC #2 PESOTUM (I-57 SBPL MEDIAN)

178+85	4.0
184+00	4.0
189+00	4.0
198+80	4.0
204+00	4.0
209+00	4.0
214+00	4.0
219+00	4.0
224+00	4.0
229+00	4.0
234+00	4.0
239+00	4.0
244+00	4.0
249+00	4.0

SUBTOTAL = 56.0

DEWITT COUNTY

LOC #3 FARMER CITY (I-74 EBPL MEDIAN)

712+00	4.0
717+00	4.0
722+75	4.0
725+50	4.0
728+00	4.0
730+50	4.0
733+00	4.0
736+00	4.0
739+00	4.0
741+50	4.0

SUBTOTAL = 40.0

TOTALS = 124.0

28000300 TEMPORARY DITCH CHECKS

STATION (EACH)

CHAMPAIGN COUNTY

LOC #2 PESOTUM (I-57 SBPL MEDIAN)

174+00	1.0
176+00	1.0
179+00	1.0
182+00	1.0
185+00	1.0
190+00	1.0
201+00	1.0
204+00	1.0
214+00	1.0
217+00	1.0
220+00	1.0
223+00	1.0
227+00	1.0
230+00	1.0
238+00	1.0
241+00	1.0
244+00	1.0
247+00	1.0

SUBTOTAL = 18.0

DEWITT COUNTY

LOC #3 FARMER CITY (I-74 EBPL MEDIAN)

715+00	1.0
718+00	1.0
721+00	1.0
726+00	1.0
728+00	1.0
731+00	1.0
736+00	1.0
739+00	1.0
742+00	1.0

SUBTOTAL = 9.0

TOTALS = 27.0

28000400 PERIMETER EROSION BARRIER

STATION (FOOT)

DOUGLAS COUNTY

LOC #1 TUSCOLA (I-57 SBDL SHOULDER)

466+50 - 504+00	3700.0
-----------------	--------

TOTALS = 3700.0

28000500 INLET & PIPE PROTECTION

STATION (EACH)

CHAMPAIGN COUNTY

LOC #2 PESOTUM (I-57 SBPL MEDIAN)

188+00	1.0
194+85	2.0
204+96	1.0
208+00	2.0
225+00	2.0
233+00	2.0
250+82	1.0

SUBTOTAL = 11.0

DEWITT COUNTY

LOC #3 FARMER CITY (I-74 EBPL MEDIAN)

723+00	1.0
734+00	1.0

SUBTOTAL = 2.0

TOTALS = 13.0