

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57&74	*	**	151	18

* D5 CABLE GUARD 2007-2
 ** CHAMPAIGN, DEWITT & DOUGLAS

SCHEDULES OF QUANTITIES

*5000792 WEED CONTROL MOWING STRIP (SPECIAL)

LOCATION	(SQ. YD.)
<u>DOUGLAS COUNTY</u>	
<u>LOC #1 TUSCOLA (I-57 SBDL SHOULDER)</u>	
LT. STA 467+25 - 503+50	1611.0
SUBTOTAL =	1611.0

CHAMPAIGN COUNTY

<u>LOC #2 PESOTUM (I-57 SBPL MEDIAN)</u>	
LT. STA 176+50 - 178+10.5	SPBGR WIDEN 116.0
LT. STA 176+50 - 217+50	SOUTH RUN 1822.0
LT. STA 216+00 - 250+50	NORTH RUN 1533.0
SUBTOTAL =	3471.0

DEWITT COUNTY

<u>LOC #3 FARMER CITY (I-74 EBPL MEDIAN)</u>	
RT. STA 712+00 - 726+50	WEST RUN 644.0
RT. STA 725+00 - 744+00	EAST RUN 845.0
SUBTOTAL =	1489.0
TOTALS =	6571.0

48101200 AGGREGATE SHOULDERS, TYPE B

LOCATION	(TON)
<u>CHAMPAIGN COUNTY</u>	
<u>LOC #2 PESOTUM (I-57 SBPL MEDIAN)</u>	
LT. STA 173+50 - 251+00	123.0
<u>DEWITT COUNTY</u>	
<u>LOC #3 FARMER CITY (I-74 EBPL MEDIAN)</u>	
RT. STA 711+50 - 744+50	53.0
TOTALS =	176.0

50800105 REINFORCEMENT BARS

STATION	(POUND)
<u>CHAMPAIGN COUNTY</u>	
<u>LOC #2 PESOTUM (I-57 SBPL MEDIAN)</u>	
194+85	16.5
208+00	41.6
225+00	1620.0
TOTALS =	1678.1
USE =	1680.0

54002020 EXPANSION BOLTS

STATION	(EACH)
<u>CHAMPAIGN COUNTY</u>	
<u>LOC #2 PESOTUM (I-57 SBPL MEDIAN)</u>	
194+85	16.0
208+00	10.0
225+00	16.0
TOTALS =	42.0

54206757 PIPE CULVERT TYPE 1, REINFORCED CONCRETE EQUIVALENT ROUND SECTION 42"

STATION	(FOOT)
<u>CHAMPAIGN COUNTY</u>	
<u>LOC #2 PESOTUM (I-57 SBPL MEDIAN)</u>	
208+00	8.5
TOTALS =	8.5
USE =	9.0

54214317 END SECTION EQUIVALENT ROUND SECTION 42"

STATION	(EACH)
<u>CHAMPAIGN COUNTY</u>	
<u>LOC #2 PESOTUM (I-57 SBPL MEDIAN)</u>	
208+00	1.0
TOTALS =	1.0

54248170 GRATE - CONCRETE FLARED END SECTION EQUIVALENT ROUND 42"

STATION	(EACH)
<u>CHAMPAIGN COUNTY</u>	
<u>LOC #2 PESOTUM (I-57 SBPL MEDIAN)</u>	
208+00	1.0
TOTALS =	1.0

54248500 CONCRETE HEADWALLS

STATION	(CU. YD.)
<u>CHAMPAIGN COUNTY</u>	
<u>LOC #2 PESOTUM (I-57 SBPL MEDIAN)</u>	
194+85	0.6
TOTALS =	0.6

50104300 CONCRETE HEADWALL REMOVAL

STATION	(CU YD)
<u>CHAMPAIGN COUNTY</u>	
<u>LOC #2 PESOTUM (I-57 SBPL MEDIAN)</u>	
208+00	0.3
TOTALS =	0.3