

F.A.D. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
SBI-4	F(B-3)	MACOUPIN	27	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT #72407				

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

80% FED. / 20% STATE

SBI ROUTE 4 (OLD IL 4) OVER HURRICANE CREEK

CONSTRUCTION  
TYPE CODE

SUMMARY OF QUANTITIES

STRUCT ROADWAY

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	X028-2A	X028-2A
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	100		100
28001000	AGGREGATE (EROSION CONTROL)	TON	30		30
28100707	STONE DUMPED RIPRAP, CLASS A4	SQ YD	640	640	
28200200	FILTER FABRIC	SQ YD	640	640	
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	223		223
35600708	HOT-MIX ASPHALT BASE COURSE WIDENING, 8"	SQ YD	110		110
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.6		0.6
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	44		44
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	180		180
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	66		66

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE  
DATE: 08/2004

DRAWN BY: FML  
CHECKED BY: JH