

F.A.D. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
SBI-4	F(B-3)	MACOUPIN	27	5
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	CONTRACT #72407		

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

80% FED. / 20% STATE

SBI ROUTE 4 (OLD IL 4) OVER HURRICANE CREEK

CONSTRUCTION
TYPE CODE

SUMMARY OF QUANTITIES

STRUCT ROADWAY

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	X028-2A	X028-2A
44000100	PAVEMENT REMOVAL	SQ YD	223		223
44000700	APPROACH SLAB REMOVAL	SQ YD	101		101
44200094	PAVEMENT PATCHING, TYPE II, 8"	SQ YD	100		100
48101200	AGGREGATE SHOULDERS, TYPE B	TON	143.8		143.8
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1	
51500100	NAME PLATES	EACH	1	1	
54001000	BOX CULVERT END SECTIONS	EACH	2	2	
54010806	PRECAST CONCRETE BOX CULVERT 8' X 6'	FOOT	84	84	
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	275		275
* 63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	75		75

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE
DATE: 08/2004

DRAWN BY: FML
CHECKED BY: JH