

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
67	S(RS-5, TS-7), L	SANGAMON	78	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

	F	HSIP		
ROADWAY	INTERSECTION OF JEFFERSON ST. AND VETERANS PKWY	INTERSECTION OF JEFFERSON ST. AND CHURCHILL DR.	STREET LIGHTING STA. 126+50 TO STA. 143+00	SIDEWALK
80% FEDERAL 20% STATE	90% FEDERAL 10% STATE	90% FEDERAL 5% STATE 5% CITY	90% FEDERAL 10% STATE	50% STATE 50% CITY

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE				
				1000	Y031-1F	Y031-1F	Y030-1E	SFTY-1B
87301275	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 12C	FOOT	64			64		
87301525	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 18 6 PAIR	FOOT	789			789		
87502700	TRAFFIC SIGNAL POST, ALUMINUM 16 FT.	EACH	4			4		
87702870	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 28 FT.	EACH	1			1		
87702880	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 30 FT.	EACH	1			1		
87702940	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 42 FT.	EACH	1			1		
87702970	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 48 FT.	EACH	1			1		
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	3			3		
87800400	CONCRETE FOUNDATION, TYPE E, 30-INCH DIAMETER	FOOT	10			10		
87800415	CONCRETE FOUNDATION, TYPE E, 36-INCH DIAMETER	FOOT	37			37		
87900200	DRILL EXISTING HANDHOLE	EACH	3			3		
88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2			2		
88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	7		5	2		
88040110	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 4-SECTION, BRACKET MOUNTED	EACH	2		2			
88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	4			4		
88040260	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 1-3-SECTION, 1-5-SECTION, BRACKET MOUNTED	EACH	2			2		
88040230	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1		1			
88040310	SIGNAL HEAD, POLYCARBONATE, LED, 3-FACE, 1-3-SECTION, 2-5-SECTION, BRACKET MOUNTED	EACH	3		1	2		
88040320	SIGNAL HEAD, POLYCARBONATE, LED, 3-FACE, 1-4-SECTION, 2-5-SECTION, BRACKET MOUNTED	EACH	1		1			
88040330	SIGNAL HEAD, POLYCARBONATE, LED, 3-FACE, 2-3-SECTION, 1-5-SECTION, BRACKET MOUNTED	EACH	1		1			
88102810	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED	EACH	4			4		
88200100	TRAFFIC SIGNAL BACKPLATE	EACH	25		15	10		
88800100	PEDESTRIAN PUSH-BUTTON	EACH	4			4		
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1			1		
89502210	MODIFY EXISTING CONTROLLER CABINET	EACH	1			1		
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	1836			1836		
89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	101			101		

\* SPECIALTY ITEMS

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION	
NAME	DATE	SUMMARY OF QUANTITIES	
		FAP 67 (IL 97/ JEFFERSON ST)	
		SECTION S(RS-5, TS-7), L	
		SANGAMON COUNTY	
SCALE	VERT. HORIZ.	DRAWN BY	
DATE		CHECKED BY	

PLOT DATE : 04/15/88  
FILE NAME : 8715L  
PLOT SCALE : 1/8"=1'-0"  
REFERENCE : 8715P