CONTRACT NO. 72851

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
67	S(RS-5,TS-7),L	SANGAMON	78	9
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SIDE ROAD, ENTRANCE AND MAILBOX TURNOUT SCHEDULE

LOCATION STATION	EXIST SURFACE TYPE	WIDTH ACROSS BACK (FT)	LENGTH (FROM EDGE OF PVT/ BIT SHLD TO LIMITS OF IMPROVEMENT) (FT)	PROP ASPHALT THICKNESS (INCH)	HOT-MIX ASPHALT SURF REM - BUTT JOINT (SQ YD)	PCC SURF REM - BUTT JOINT (SQ YD)	LEVEL BINDER (MM) N90 (1") (TON)	HOT-MIX ASPHALT SURF CSE "D" N90 (1 1/2") (TON)	INCIDENTAL HOT-MIX ASPHALT SURF (TON)	BIT MAT PRIME CT (TON)	AGGREGATE PRIME CT (TON)
SIDE ROAD RT. STA. 141+23	BIT	22	25	VAR. 1 1/2-2 1/2	67.56	-	-	-	7.57	0.03	-
CHURCH HILL ST. RT. STA. 143+21.20	CONC/BIT	36	98	VAR. 1 1/2-2 1/2	-	240.00	28.30	52.52	-	0.24	1.25
CHURCH HILL ST. LT. STA. 143+21.20	CONC/BIT	49	67	VAR. 1 1/2-2 1/2	-	272.78	14.94	33.86	-	0.15	0.81
WESTWOOD TERRACE RT. STA. 145+37	CONC/BIT	24	46	VAR. 1 1/2-2 1/2	-	172.05	-	-	19.27	0.07	0.34
				TOTAL	68	685	43.5	87	27	0.50	2.5

AGGREGATE SHOULDER SCHEDULE

LOCATION STATION TO STATION	LENGTH (FT)	AGGREGATE SHOULDERS, WIDTH (FT)	AGGREGATE SHOULDERS, TYPE B (TON)
FAP 67 (IL 97/ JEFFERSON ST.)			
RT. STA. 117+93.00 TO RT. STA. 120+53.03 EAST BOUND	260.03	3	19.75
LT. STA. 117+93.00 TO LT. STA. 120+53.03 WEST BOUND	260.03	3	26.71
RT. STA. 121+51.17 TO RT. STA. 123+49.26 EAST BOUND	198.09	3	18.36
LT. STA. 121+51.17 TO LT. STA. 123+82.44 WEST BOUND	231.27	3	15.03
		TOTAL	74

GUARDRAIL SCHEDULE

LOCATION STATION TO STATION	GUARDRAIL REMOVAL (FOOT)	TRAF BAR TERM, TY6B (EACH)	SPBGR TYPE A (FOOT)	TRAF BAR TERM, TY1 SPL (TANG) (EACH)	TERM MARKER DIRECT APPLIED (EACH)	GUARDRAIL MARKERS, TYPE A (EACH)
FAP 67 (IL 97/ JEFFERSON ST.)						
RT. STA. 122+38.15 TO RT. STA. 123+69.40 EASTBOUND	92	1	37.5	1	1	1
LT. STA. 126+67.10 TO LT. STA. 129+23.35 WESTBOUND	92	1	162.5	1	1	1
TOTAL	184	2	200	2	2	2

MEDIAN SCHEDULE

LOCATION STATION TO STATION	MEDIAN SURF REM & REPL (SQ FT)	MEDIAN REMOVAL (SQ FT)	CORRUGATED MEDIAN (SQ FT)	STABILIZED SUB-BASE 4" (SQ YD)
FAP 67 (IL 97/ JEFFERSON ST.)				
STA. 130+93.00 TO STA. 131+07.00	62	-	-	6.89
STA. 141+35.08 TO STA. 142+80.08		1,121	1057	124.56
STA. 130+94.00 TO STA. 131+00.00	16			
STA. 139+25.00 TO STA. 139+30.00	14			
TOTAL	92	1121	1057	132

COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT SCHEDULE

LOCATION STATION TO STATION	(FOOT)
FAP 67 (IL 97/ JEFFERSON ST.)	
4' RT. STA. 130+94.00 TO 4' RT. STA. 131+00.00	6.0
4' RT. STA. 139+25.00 TO 4' RT. STA. 139+30.00	5.0
TOTAL	11.0

NOTE: STATION FOR CONRETE CURB AND GUTTER REMOVAL AND REPLACEMENT ARE APPROXIMATE.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
FAP 67 (IL 97/ JEFFERSON ST)
SECTION S(RS-5,TS-7),L
SANGAMON COUNTY

SCALE: VERT. HORIZ.
DATE
DRAWN BY
CHECKED BY

PLOT DATE = $DATE$
FILE NAME = $FILEL$
PLOT SCALE = $SCALE$
REFERENCE = REF