CONTRACT NO. 72851

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
67	S(RS-5,TS-7),L	SANGAMON	78	10
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SHORT - TERM PAVEMENT MARKING & WORK ZONE PAVEMENT MARKING REMOVAL SCHEDULE

LOCATION STATION TO STATION	DESCRIPTION	LENGTH (FT)	NUMBER OF LANE LINES	QUANTITY: SHORT - TERM PAVEMENT MARKING (WHITE) (FT)	QUANTITY: SHORT - TERM PAVEMENT MARKING (YELLOW) (FT)	QUANTITY: WORK ZONE PAVT MR REM (SQ FT)
FAP 67 (IL 97/ JEFFERSON ST.)						
EB STA. 127+44.10 TO STA. 142+70.50	LANE LINE, SKIP-DASH	1526.40	1	457.9	-	50.4
EB STA. 141+78.00 TO STA. 142+68.00	TURN LANE LINE, SOLID	90.00	1	27.0	-	3.0
WB STA. 127+60.84 TO STA. 142+56.00	LANE LINE, SKIP-DASH	1495.16	1	448.6	-	49.3
WB STA. 130+94.00 TO STA. 132+00.00	TURN LANE LINE, SOLID	106.00	1	31.8	-	3.5
WB STA. 138+72.00 TO STA. 140+00.00	TURN LANE LINE, SOLID	128.00	1	38.4	-	4.2
WB STA. 143+70.00 TO STA. 150+26.00	LANE LINE, SKIP-DASH	656.00	1	196.8	-	21.6
WB STA. 143+70.00 TO STA. 145+14.00	TURN LANE LINE, SOLID	144.00	1	43.2	-	4.8
WB STA. 145+95.00 TO STA. 147+27.00	TURN LANE LINE, SOLID	132.00	1	39.6	-	4.4
EB STA. 143+66.00 TO STA. 150+26.00	LANE LINE, SKIP-DASH	660.00	1	198.0	-	21.8
STA. 143+66.00 TO STA. 145+13.00	MEDIAN LINE, SOLID	147.00	2	-	88.2	9.7
STA. 145+97.50 TO STA. 148+00.00	MEDIAN LINE, SOLID	202.50	2	-	121.5	13.4
STA. 148+00.00 TO STA. 150+26.00	BI-DIRECTIONAL LANE LINE, SKIP-DASH	226.00	2	-	135.6	14.9
CHURCHILL DRIVE (SOUTH)						
STA. 29+71.52 TO STA. 30+48.00	LANE LINE, SOLID	76.48	2	45.9	-	5.0
CHURCHILL DRIVE (NORTH)						
STA. 50+51.00 TO STA. 51+02.50	LANE LINE, SOLID	51.50	1	15.5	-	1.7
			SUB-TOTAL	1542.7	345.3	
			TOTAL	1888		208

NOTE: SHORT-TERM PAVEMENT MARKING QUANTITIES ARE AS FOLLOWS:
BITUMINOUS OVERLAY SECTION THREE APPLICATIONS

DETECTABLE WARNINGS SCHEDULE

LOCATION STATION	(SQ FT)
RT. STA. 141+03	10
RT. STA. 141+28	10
RT. STA. 142+94	10
RT. STA. 143+55	10
RT. STA. 143+62	10
RT. STA. 143+87	10
TOTAL	60

KEY: EB = EASTBOUND LANES
WB = WESTBOUND LANES

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
FAP 67 (IL 97/ JEFFERSON ST)
SECTION S(RS-5,TS-7),L
SANGAMON COUNTY

SCALE: VERT. HORIZ.
DATE
DRAWN BY
CHECKED BY

PLOT DATE = $DATE$
FILE NAME = $FILEL$
PLOT SCALE = $CSCALE$
USER NAME = $USER$