

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
67	SIRS-5,TS-7),L	SANGAMON	78	12
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

TEMPORARY PAVEMENT MARKING - LINE 6" SCHEDULE					
LOCATION STATION TO STATION	DESCRIPTION	LENGTH (FT)	NUMBER OF LANE LINES	QUANTITY (WHITE) (FT)	
FAP 67 (IL 97/ JEFFERSON ST.)					
WB STA. 130+94.00 TO STA. 132+00.00	TURN LANE LINE, SOLID	106.00	1	106.0	
WB STA. 138+72.00 TO STA. 140+00.00	TURN LANE LINE, SOLID	128.00	1	128.0	
EB STA. 141+78.00 TO STA. 142+68.00	TURN LANE LINE, SOLID	90.00	1	90.0	
WB STA. 143+70.00 TO STA. 145+14.00	TURN LANE LINE, SOLID	144.00	1	144.0	
WB STA. 145+95.00 TO STA. 147+27.00	TURN LANE LINE, SOLID	132.00	1	132.0	
CHURCHILL DRIVE (SOUTH)					
STA. 29+71.52 TO STA. 30+48.00	LANE LINE, SOLID	76.48	1	76.5	
CHURCHILL ROAD (NORTH)					
STA. 50+51.00 TO STA. 51+02.50	LANE LINE, SOLID	51.50	1	51.5	
				TOTAL	728.0

TEMPORARY PAVEMENT MARKING - LINE 24" SCHEDULE		
LOCATION STATION	DESCRIPTION	QUANTITY (WHITE) (FT)
FAP 67 (IL 97/ JEFFERSON ST.)		
EB STA. 142+68.0 LEFT TURN LANE	STOP BAR, SOLID	12
EB STA. 142+70.5 MAIN LINE	STOP BAR, SOLID	24
WB STA. 143+70.0 MAIN LINE	STOP BAR, SOLID	36
CHURCHILL DRIVE (SOUTH)		
STA. 30+48.00 NORTHBOUND	STOP BAR, SOLID	24
STA. 30+44.50 RIGHT TURN LANE	STOP BAR, SOLID	18
		TOTAL
		114

TEMPORARY PAVEMENT MARKING - LINE 12" SCHEDULE				
LOCATION STATION TO STATION	DESCRIPTION	QUANTITY (WHITE) (FT)	QUANTITY (YELLOW) (FT)	
FAP 67 (IL 97/ JEFFERSON ST.)				
STA. 143+66.00 TO STA. 145+13.00	MEDIAN DIAGONALS, SOLID	-	79	
STA. 145+97.50 TO STA. 148+00.00	MEDIAN DIAGONALS, SOLID	-	122	
		SUB-TOTAL	0	201.0
		TOTAL	201.0	

TEMPORARY PAVEMENT MARKING, LETTERS AND SYMBOLS SCHEDULE			
LOCATION STATION TO STATION	DESCRIPTION	QUANTITY (WHITE) (SO FT)	
FAP 67 (IL 97/ JEFFERSON ST.)			
WB STA. 131+19.00 TO STA 131+95.00	LEFT TURN ARROWS (2 @ 76' CTS)	31.2	
WB STA. 139+06.00 TO STA. 139+95.00	LEFT TURN ARROWS (2 @ 89' CTS)	31.2	
EB STA. 141+83.00 TO STA. 142+44.00	LEFT TURN ARROWS (2 @ 61' CTS)	31.2	
WB STA. 143+94.00 TO STA. 144+95.00	LEFT TURN ARROWS (2 @ 101' CTS)	31.2	
WB STA. 146+23.00 TO STA. 147+22.00	LEFT TURN ARROWS (2 @ 99' CTS)	31.2	
		TOTAL	156.0

KEY: EB = EASTBOUND LANES
WB = WESTBOUND LANES

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
FAP 67 (IL 97/ JEFFERSON ST)
SECTION S(RS-5, TS-7), L
SANGAMON COUNTY
 SCALE: VERT. _____
 DATE: _____
 HORIZ. _____
 DRAWN BY _____
 CHECKED BY _____