

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
67	SIRS-5, TS-7, L	SANGAMON	78	13
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

POLYUREA PAVEMENT MARKING, SPECIAL - LINE 5" SCHEDULE						
LOCATION STATION TO STATION	DESCRIPTION	LENGTH (FT)	NUMBER OF LANE LINES	QUANTITY		
				(WHITE) (FT)	(YELLOW) (FT)	
FAP 67 (IL 97/ JEFFERSON ST.)						
WB STA. 127+60.84 TO STA. 128+17.00	OUTSIDE EDGE LINE, SOLID	56.16	1	56.16	-	
WB STA. 127+60.84 TO STA. 130+32.00	MEDIAN LINE, SOLID	271.16	1	-	271.16	
EB STA. 127+44.10 TO STA. 130+32.00	MEDIAN LINE, SOLID	287.9	1	-	287.9	
EB STA. 127+44.10 TO STA. 127+84.00	OUTSIDE EDGE LINE, SOLID	39.9	1	39.9	-	
WB STA. 130+93.00 TO STA. 133+85.00	MEDIAN LINE, SOLID	292.00	1	-	292.0	
EB STA. 130+93.00 TO STA. 133+85.00	MEDIAN LINE, SOLID	292.00	1	-	292.0	
WB STA. 134+35.00 TO STA. 138+18.00	MEDIAN LINE, SOLID	383.00	1	-	383.0	
EB STA. 134+35.00 TO STA. 138+18.00	MEDIAN LINE, SOLID	383.00	1	-	383.0	
WB STA. 138+77.00 TO STA. 142+76.00	MEDIAN LINE, SOLID	399.00	1	-	399.0	
EB STA. 138+77.00 TO STA. 142+70.00	MEDIAN LINE, SOLID	393.00	1	-	393.0	
STA. 143+66.00 TO STA. 145+13.00	MEDIAN LINE, SOLID DOUBLE	147.00	2	-	630.0	
STA. 145+97.50 TO STA. 148+00.00	MEDIAN LINE, SOLID DOUBLE	202.50	2	-	837.0	
WB STA. 148+00.00 TO STA. 148+87.00	MEDIAN LINE, SOLID DOUBLE	87.00	2	-	174.0	
EB STA. 148+00.00 TO STA. 150+26.00	BI-DIRECTIONAL LANE LINE, SOLID	226.00	1	-	226.0	
WB STA. 148+87.00 TO STA. 150+26.00	BI-DIRECTIONAL LANE LINE, SOLID	139.00	1	-	139.0	
CHURCHILL DRIVE (SOUTH)						
STA. 29+71.52 TO STA. 30+48.00	LANE LINE, SOLID DOUBLE	76.48	2	-	153.0	
SUB-TOTAL				96.06	4860.06	
TOTAL				4956		

POLYUREA PAVEMENT MARKING, SPECIAL - LINE 6" SCHEDULE				
LOCATION STATION TO STATION	DESCRIPTION	LENGTH (FT)	NUMBER OF LANE LINES	QUANTITY
				(WHITE) (FT)
FAP 67 (IL 97/ JEFFERSON ST.)				
WB STA. 130+94.00 TO STA. 132+00.00	TURN LANE LINE, SOLID	106.00	1	106.0
WB STA. 138+72.00 TO STA. 140+00.00	TURN LANE LINE, SOLID	128.00	1	128.0
EB STA. 141+78.00 TO STA. 142+68.00	TURN LANE LINE, SOLID	90.00	1	90.0
WB STA. 143+70.00 TO STA. 145+14.00	TURN LANE LINE, SOLID	144.00	1	144.0
WB STA. 145+95.00 TO STA. 147+27.00	TURN LANE LINE, SOLID	132.00	1	132.0
CHURCHILL DRIVE (SOUTH)				
STA. 29+71.52 TO STA. 30+48.00	LANE LINE, SOLID	76.48	1	76.5
CHURCHILL ROAD (NORTH)				
STA. 50+51.00 TO STA. 51+02.50	LANE LINE, SOLID	51.50	1	51.5
TOTAL				728.0

POLYUREA PAVEMENT MARKING, SPECIAL - LINE 12" SCHEDULE			
LOCATION STATION TO STATION	DESCRIPTION	QUANTITY	QUANTITY
		(WHITE) (FT)	(YELLOW) (FT)
FAP 67 (IL 97/ JEFFERSON ST.)			
STA. 143+66.00 TO STA. 145+13.00	MEDIAN DIAGONALS, SOLID	-	79
STA. 145+97.50 TO STA. 148+00.00	MEDIAN DIAGONALS, SOLID	-	122
SUB-TOTAL		0	201
TOTAL		201	

POLYUREA PAVEMENT MARKING, SPECIAL LINE 24" SCHEDULE		
LOCATION STATION	DESCRIPTION	QUANTITY (WHITE) (FT)
FAP 67 (IL 97/ JEFFERSON ST.)		
EB STA. 142+68.0 LEFT TURN LANE	STOP BAR, SOLID	12
EB STA. 142+70.5 MAIN LINE	STOP BAR, SOLID	24
WB STA. 143+70.0 MAIN LINE	STOP BAR, SOLID	36
CHURCHILL DRIVE (SOUTH)		
STA. 30+48.00 NORTHBOUND	STOP BAR, SOLID	24
STA. 30+44.50 RIGHT TURN LANE	STOP BAR, SOLID	18
TOTAL		114

KEY: EB = EASTBOUND LANES
WB = WESTBOUND LANES

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
FAP 67 (IL 97/ JEFFERSON ST)
SECTION S(RS-5, TS-7), L
SANGAMON COUNTY

SCALE: VERT. _____
HORIZ. _____

DATE: _____ DRAWN BY: _____
CHECKED BY: _____