

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
662	*	MACOUPIN	68	8
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

AGGREGATE SHOULDERS

LOCATION	LENGTH	AVE WIDTH	AGGREGATE SHOULDERS
	FOOT	FOOT	TON
LT STA 441+00.00 TO LT STA 441+85.00	85.00	4.00	5.00
LT STA 441+85.00 TO LT STA 442+85 - SIDE ROAD OMISSION			
LT STA 442+85.00 TO LT STA 443+00	15.00	4.00	0.88
LT STA 443+00 TO LT STA 444+00	100.00	4.30	17.57
LT STA 444+00 TO LT STA 445+00	100.00	4.74	32.97
LT STA 445+00 TO LT STA 446+00	100.00	5.03	48.23
LT STA 446+00 TO LT STA 446+29.30	29.30	5.19	16.86
LT STA 446+29.30 TO LT STA 447+78.30 - BRIDGE OMISSION			
LT STA 447+78.30 TO LT STA 448+00	21.70	5.01	7.64
LT STA 448+00 TO LT STA 449+00	100.00	4.72	24.68
LT STA 449+00 TO LT STA 450+00	100.00	4.24	9.84
LT STA 450+00 TO LT STA 452+00	200.00	4.00	11.76
RT STA 441+00 TO RT STA 441+28	28.00	4.00	1.64
RT STA 441+28 TO RT STA 442+67 - SIDE ROAD OMISSION			
RT STA 442+67.00 TO RT STA 443+00	33.00	4.00	1.94
RT STA 443+00 TO RT STA 444+00	100.00	4.30	17.57
RT STA 444+00 TO RT STA 445+00	100.00	4.74	32.97
RT STA 445+00 TO RT STA 446+00	100.00	5.03	48.23
RT STA 446+00 TO RT STA 446+29.30	29.30	5.19	16.86
RT STA 446+29.30 TO RT STA 447+78.30 - BRIDGE OMISSION			
RT STA 447+78.30 TO RT STA 448+00	21.70	5.01	7.64
RT STA 448+00 TO RT STA 449+00	100.00	4.72	24.68
RT STA 449+00 TO RT STA 450+00	100.00	4.24	9.66
RT STA 450+00 TO RT STA 450+35 - ENTRANCE OMISSION			
RT STA 450+35 TO RT STA 452+00	165.00	4.00	9.70
TOTAL =			346.32

HMA BASE COURSE WIDENING, 10"

LOCATION	LENGTH	BIT PAY WIDTH	HMA BASE COURSE WID, 10"
	FOOT	FOOT	SO YD
LT STA 442+75.00 TO LT STA 442+85.00	10.00	0.0 - 3.0	1.67
LT STA 442+85.00 TO LT STA 446+29.30	344.30	2.0	76.51
LT STA 446+29.30 TO LT STA 447+78.30 - BRIDGE OMISSION			
LT STA 447+78.30 TO LT STA 450+71.00	292.70	2.0	65.04
LT STA 450+71.00 TO LT STA 450+95.00	24.00	2.0 - 6.0	10.67
LT STA 450+95.00 TO LT STA 451+10.00	15.00	7.0	11.67
LT STA 451+10.00 TO LT STA 451+50.00	40.00	7.0 - 2.0	20.00
RT STA 442+57.00 TO RT STA 442+67.00	10.00	0.0 - 3.0	1.67
RT STA 442+67.00 TO RT STA 446+29.30	362.30	3.0 - 2.0	80.51
RT STA 446+29.30 TO RT STA 447+78.30 - BRIDGE OMISSION			
RT STA 447+78.30 TO RT STA 450+35.00	256.70	2.00	57.04
RT STA 450+35.00 TO RT STA 450+76.00	41.00	2.0 - 3.8	13.21
RT STA 450+76.00 TO RT STA 451+00.00	24.00	2.00	7.73
NOTE: PRIME COAT QUANTITIES ARE INCLUDED IN RESURFACING SCHEDULE			
TOTAL =			345.72

GUARDRAIL SCHEDULE

LOCATION	TBT T-1 SPL (TANGENT)	TERMINAL MARKER DIR. APPL.	TBT T-6	SPBGR T-A	GUARDRAIL MARKERS T-A	GUARDRAIL REMOVAL
	EACH	EACH	EACH	FOOT	EACH	FOOT
RT STA 442+82.50 TO RT STA 443+32.50	1	1			-	
RT STA 443+32.50 TO RT STA 446+07.50				275.0	5	
RT STA 446+07.50 TO RT STA 446+53.10			1			109
NW Quadrant						
RT STA 447+37.10 TO RT STA 447+82.70			1		-	
RT STA 447+82.70 TO RT STA 449+32.70				150.0	3	
RT STA 449+32.70 TO RT STA 449+82.70	1	1				109
SW Quadrant						
LT STA 442+99.90 TO LT STA 443+49.90	1	1			-	
LT STA 443+49.90 TO LT STA 446+24.90				275	3	
LT STA 446+24.90 TO LT STA 446+70.50			1			109
NE Quadrant						
LT STA 447+54.50 TO LT STA 448+00.10			1		-	
LT STA 448+00.10 TO LT STA 450+50.10				250.0	4	
LT STA 450+50.10 TO LT STA 451+00.10	1	1				109
SE Quadrant						
TOTAL =	4	4	4	950	15	436

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES

SCALE: VERT. / HORIZ.
DATE

DRAWN BY
CHECKED BY