

S U M M A R Y O F Q U A N T I T I E S

CODE NO.	ITEM	LOCATION #1	LOCATION #2	LOCATION #3	LOCATION #4	UNIT	100% STATE
							I000
							TOTAL QTY
40600200	BITUMINOUS MATERIALS (PRIME COAT)	0.8	0.8	0.9	3.3	TON	5.8
40600300	AGGREGATE (PRIME COAT)	4.0	4.0	4.9	17.1	TON	30.0
40600895	CONSTRUCTING TEST STRIP	0.25	0.25	0.25	0.25	EACH	1
40600990	TEMPORARY RAMP	27	27	13	27	SQ YD	94
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX D, N70	168	168	207.2	716.4	TON	1,259.6
44000155	HOT-MIX ASPHALT SURFACE REMOVAL 1 1/2"	2,000	2,000	2,467	8,528	SQ YD	14,995
48101200	AGGREGATE SHOULDERS, TYPE B			43.9	18.3	TON	62.2
67100100	MOBILIZATION	0.25	0.25	0.25	0.25	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	0.25	0.25	0.25	0.25	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	0.25	0.25	0.25	0.25	L SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501				1	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	75	150	99	320	FOOT	644
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	1,688	3,232	3,066	10,127	FOOT	18,113

QUANTITIES  
FAP 325 (IL 16)  
SECTION (2)I-5  
MONTGOMERY COUNTY