

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
663	(84-3HB-2)J	SANGAMON	6	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES

LOCATION OF WORK:				STEVENSON DRIVE	
FAP 663 (STEVENSON DR.) OVER FAI 55				CONSTRUCTION TYPE CODE	
SOUTHEAST EDGE OF SPRINGFIELD				SFTY-3J	
SANGAMON COUNTY				URBAN 100% STATE	
PAYCODE	PAY ITEM DESCRIPTION	UNITS	TOTAL QUANTITY		
44003700	MEDIAN REMOVAL SPECIAL	SQ FT	16	16	
44000500	COMBINATION CONCRETE CURB AND GUTTER REMOVAL	FOOT	27.5	27.5	
44000600	CONCRETE SIDEWALK REMOVAL	SQ FT	7.5	7.5	
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	39.4	39.4	
60600105	CONCRETE CURB,	FOOT	8	8	
60604300	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.12 (VARIABLE WIDTH GUTTER FLAG)	FOOT	27.5	27.5	
63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	37.5	37.5	
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	3	3	
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	3	3	
67100100	MOBILIZATION	L SUM	1	1	
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	

DISTRICT SIX

EXAMINED Jan 30 2007
Jonni J. Haasi
 OPERATIONS ENGINEER

EXAMINED Jan 30 2007
WRJ
 PROGRAM IMPLEMENTATION ENGINEER

EXAMINED Jan 30 2007
WRJ
 PROGRAM DEVELOPMENT ENGINEER

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 FAP 663 (STEVENSON DR.) OVER FAI 55
 SECTION (84-3HB-2)J
 SANGAMON COUNTY

SCALE: VERT. _____
 HORIZ. _____
 DATE _____

DRAWN BY RTS
 CHECKED BY _____

Rev.