

FAP RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
**	*	SANGAMON	14	8

STA.	TO STA.
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT

* D6 DIRKSEN/CLEARLAKE RES 2007
 ** FAP 67 - CLEAR LAKE
 FAP 75, 668 - DIRKSEN

PAVING SCHEDULE						
LOCATION	STATION RANGE	PRIME COAT		POLY. HOT-MIX ASPHALT SURFACE COURSE MIX "D", N90 TONS	INCIDENTAL HOT-MIX ASPHALT RESURFACING TONS	HOT-MIX ASPHALT SURFACE REMOVAL - TWO INCHES SQUARE YARDS
		BIT. MAT. TONS	AGGREGATE TONS			
CLEARLAKE/ DIRKSEN	INTERSECTION	0.89	3.13	175.2		1,564.0
CLEARLAKE, W. B.	128+15 TO 132+02	0.68	2.39	133.8		1,195.0
CLEARLAKE, W. B.	20+19 TO 21+20	0.38	1.34	75.0		669.6
CLEARLAKE, E. B.	128+15 TO 132+02	1.05	3.70	207.2		1,850.4
CLEARLAKE, E. B.	20+19 TO 20+80	0.19	0.66	37.0		330.8
DIRKSEN, S. B.	154+50 TO 163+02	1.55	5.44	304.8		2,721.0
DIRKSEN, S. B.	164+38 TO 167+35	0.81	2.84	159.1		1,420.8
DIRKSEN, N. B.	154+50 TO 163+02	2.35	8.24	461.2		4,117.6
DIRKSEN, N. B.	164+38 TO 167+35	0.59	2.06	115.4		1,030.4
SIDEROADS		0.08	0.28		15.6	138.9
ENTRANCES		0.08	0.28		15.6	138.9
TOTALS		8.7	30.4	1669	32	15178

RAISED REFLECTIVE PAVEMENT MARKER		
LOCATION	RAISED REFL. ECTIVE PAYMENT MARKER (EACH)	RAISED REFL. ECTIVE PAYMENT MARKER REMOVAL (EACH)
S. LEG DIRKSEN PARKWAY	49	49
N. LEG DIRKSEN PARKWAY	19	19
W. LEG CLEAR LAKE AVENUE	23	23
E. LEG CLEAR LAKE AVENUE	12	12
TOTALS	103	103

HMA SURFACE REMOVAL - BUTT JOINT			
STATION	ROADWAY	DIRECTION	UNITS - SQ YD
154+50	DIRKSEN	NORTHBOUND	28
	DIRKSEN	SOUTHBOUND	30
167+35	DIRKSEN	NORTHBOUND	30
	DIRKSEN	SOUTHBOUND	30
128+15	CLEARLAKE	EASTBOUND	27
	CLEARLAKE	WESTBOUND	27
20+80	CLEARLAKE	EASTBOUND	36
	CLEARLAKE	WESTBOUND	56
SIDEROADS			57
ENTRANCES			57
TOTAL			378

ADJUSTMENTS			
ROADWAY	QUADRANT	WATER VALVES TBA - EACH	MANHOLES TBA - EACH
CLEARLAKE	WEST LEG	3	4
CLEARLAKE	EAST LEG		5
TOTALS		3	9

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
**SECTION: D6 DIRKSEN/CLEARLAKE
 RES 2007
 SANGAMON COUNTY**