

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
91	•	COLES	5	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
• D7 SIGNAL MODERNIZATION 2007-4				

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	YO31-1F 90% FED. 10% STATE URBAN	
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	84	84	
42400800	DETECTABLE WARNINGS	SQ FT	10	10	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	6	6	
60605100	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (ABUTTING EXISTING PAVEMENT)	FOOT	6	6	
67100100	MOBILIZATION	L SUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	441	441	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	54	54	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	118	118	
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	25	25	
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1835	1835	
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	737	737	
87502720	TRAFFIC SIGNAL POST, ALUMINUM 18 FT.	EACH	2	2	
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	3	3	
87900200	DRILL EXISTING HANDHOLE	EACH	1	1	
88102810	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED	EACH	4	4	
88800100	PEDESTRIAN PUSH-BUTTON	EACH	8	8	
89500100	RELOCATE EXISTING SIGNAL HEAD	EACH	4	4	
89500200	RELOCATE EXISTING PEDESTRIAN SIGNAL HEAD	EACH	1	1	
89502210	MODIFY EXISTING CONTROLLER CABINET	EACH	1	1	
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	1509	1509	
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	1	1	

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT.
HORIZ.
DATE

DRAWN BY
CHECKED BY

PLT DATE * * * * *
PLT SCALE * * * * *
USER NAME * * * * *