

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
F.A.I. 70	*	ST. CLAIR	99	80
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT- 1M-70		
* 82-3HVB-3R-5			SHEET S-3 OF S-22	
CONTRACT NO. 76985				

BRIDGE REHABILITATION AND RETROFIT:

1. Remove existing deck parapet, sidewalk and outermost 3' to 4' of concrete deck as required at the following locations and replace with new parapet (6 spans):
Spans T1 through T6
2. Per Sheet S17, remove existing hot mix asphalt bituminous overlay, perform concrete deck repairs (partial depth) as necessary, scarify top 1/2" of existing concrete deck, and add new microsilica concrete overlay at the following locations (6 spans):
Spans T1 through T6
3. Install new drainage scuppers as indicated at the following spans (5 spans):
T1 T2 T4 T5 T6
4. Remove existing bridge deck joints and replace with new neoprene joint at the following abutment (1 location):
T6
5. Resurface adjacent hot mix asphalt roadway surface at the following abutment (1 location):
T6
6. Clean and paint selected portions of the steel superstructure including bottom portions of girders and all steel in the vicinity of deck joints.
Spans T1 through T6
7. Perform vertical stiffener intersection modifications on the following spans (6 spans)
Spans T1 through T6

DATE: 1/24/2007
FILENAME: P:\2001\1201-1300\2001.1240\Drafting\RoadwayRehab_AT\Ramp\T_SCOPE.dgn

DESIGNED	JEL
CHECKED	HH
DRAWN	CLK
CHECKED	JEL

SCOPE OF WORK

REVISIONS		STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION REHABILITATION AND RETROFIT REPAIRS FAI ROUTE 70 POPLAR STREET BRIDGE APPROACHES ST. CLAIR COUNTY STRUCTURE NO. 082-0146 (Ramp T) SCALE: N.T.S. DATE: 02/01/2007
NAME	DATE	