

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
F.A.I. 70	*	ST. CLAIR	99	82
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT- IM-70		

* 82-3HVB-3R-5 SHEET S-5 OF S-22
 CONTRACT NO. 76985

TOTAL BILL OF MATERIAL

ITEM	UNIT	SUPERSTRUCTURE	SUBSTRUCTURE	TOTAL
Concrete Removal	CU YD	287	---	287
Concrete Superstructure	CU YD	260	---	260
Reinforcement Bars, Epoxy coated	POUND	37,840	---	37,840
Bridge Deck Hydro-Scarification-1/2"	SQ YD	1,402	---	1,402
Bridge Deck Microsilica Concrete Overlay-2 1/2"	SQ YD	1,588	---	1,588
Bridge Deck Grooving	SQ YD	1,588	---	1,588
Protective Coat	SQ YD	2,525	---	2,525
Polymer Concrete	CU FT	10	---	10
Neoprene Expansion Joint, 4"	FOOT	26	---	26
Hot Mix Asphalt Surface Removal (Deck)	SQ YD	1,402	---	1,402
Drainage Scuppers, DS12	EACH	5	---	5
Protective Shield	SQ YD	320	---	320
Curb Removal (Special)	FOOT	7.5	---	7.5
Cleaning and Painting Steel Bridge, No. 2	L SUM	1	---	1
Containment & Disposal of Lead Paint Cleaning Residues, No. 2	L SUM	1	---	1
Stiffener Intersection Modification	EACH	280	---	280
Crack Extension Modifications	EACH	5	---	5

DATE: 1/26/2007 FILENAME: P:\2001\1201-1300\2001.1240\Drafting\Roadway\Rehab_AT\Temp\T-Sched.dgn

DESIGNED	JEL
CHECKED	MJS
DRAWN	CLK
CHECKED	JEL

REVISIONS	
NAME	DATE

BILL OF MATERIAL
 STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION
 REHABILITATION AND RETROFIT REPAIRS
 FAI ROUTE 70
 POPLAR STREET BRIDGE APPROACHES
 ST. CLAIR COUNTY

STRUCTURE NO. 082-0146 (Ramp T)
 SCALE: N.T.S.
 DATE: 02/01/2007