

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310		MADISON	418	99
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SIGN SCHEDULE									
STA	OFFSET	SIGN NUMBER	DESCRIPTION	DIMENSIONS	SIGN PANEL TYPE 1 SQ FT	SIGN PANEL TYPE 2 SQ FT	SIGN PANEL TYPE 3 SQ FT	WOOD POST FOOT	
FAP 310									
18+430	RT		OVERHEAD	16' X 11' 13' X 11.5'			176 149.5		
30+213	LT		BRIDGE	13' X 9'			117		
30+760	LT		OVERHEAD	13' X 11.5' 17.5' X 8.5'			149.5 148.75		
30+921	LT	XM-1	COUNTY	1.5' X 1.5'	2.25			15	
	RT	XM-1	COUNTY	1.5' X 1.5'	2.25			15	
31+025	RT	R2-4a	65/45	4' X 8'			32	22	
31+150	RT	R2-I104	55	4' X 8'			32	22	
31+675	RT		WIDE FLANGE	16.5' X 8.5'			140.25		
31+950	LT		WIDE FLANGE	17.5' X 8.5'			148.75		
32+530	LT	XM-1	COUNTY	1.5' X 1.5'	2.25			15	
	RT	XM-1	COUNTY	1.5' X 1.5'	2.25			15	
32+875	RT		WIDE FLANGE	16.5' X 8.5'			140.25		
33+150	LT		WIDE FLANGE	17.5' X 8.5'			148.75		
33+600	LT	R2-4a	65/45	4' X 8'			32	22	
33+725	LT	R2-I104	55	4' X 8'			32	22	
34+025	RT		OVERHEAD	13' X 11.5' 16.5' X 8.5'			149.5 140.25		
34+140	LT	XM-1	COUNTY	1.5' X 1.5'	2.25			15	
	RT	XM-1	COUNTY	1.5' X 1.5'	2.25			15	
34+574	RT		BRIDGE	13' X 9'			117		
FOSTERBURG RD									
65+175	LT		WIDE FLANGE	13' X 9'			117		
4+900	LT	M1-I100	IL 255	3.75' X 3'		11.25		18	
		M3-1	NORTH	2.5' X 1.25	3.125				
		M5-1L	LEFT ARROW	2.5' X 1.5'	3.75				
RAMP 3									
1+150	RT	R5-I100	BUCKLE UP	4' X 4.5'		18		17	
1+300	LT	W4-1L	MERGE	4' X 4'		16		17	
RAMP 4									
1+275	RT	W13-3	ADVISORY SPD	4' X 5'		20		18	
1+375	LT	R5-1A	WRONG WAY	3' X 2'	6			15	
	RT	R5-1A	WRONG WAY	3' X 2'	6			15	
1+475	LT	R5-1	DO NOT ENTER	2.5' X 2.5'	6.25			15	
	RT	R5-1	DO NOT ENTER	2.5' X 2.5'	6.25			15	
SEMINARY RD									
4+825	RT		WIDE FLANGE	13' X 9'			117		
4+900	LT	M1-I100	IL 255	3.75' X 3'		11.25		18	
		M3-3	SOUTH	2.5' X 1.25	3.125				
		M5-1L	LEFT ARROW	2.5' X 1.5'	3.75				
RAMP 1									
1+100	RT	R5-I100	BUCKLE UP	4' X 4.5'		18		17	
1+350	LT	W4-1L	MERGE	4' X 4'		16		17	
RAMP 2									
1+275	RT	W13-3	ADVISORY SPD	4' X 5'		20		18	
1+425	LT	R5-1A	WRONG WAY	3' X 2'	6			15	
	RT	R5-1A	WRONG WAY	3' X 2'	6			15	
1+550	LT	R5-1	DO NOT ENTER	2.5' X 2.5'	6.25			15	
	RT	R5-1	DO NOT ENTER	2.5' X 2.5'	6.25			15	
TOTALS					76.25	130.5	2087.5	438	

\* DATES \*  
 \* FILE NAME \*  
 \* PLOT SCALE \*  
 \* USER NAME \*

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p align="center"> <b>SCHEDULES</b>  <b>FAP 310</b>  <b>SECTIONS 60-14-2 &amp; 60-14-2B</b>  <b>MADISON COUNTY</b> </p> <p>           SCALE: VERT. _____            HORIZ. _____            DATE _____         </p> <p align="right">           DRAWN BY _____            CHECKED BY _____         </p>