

WIDE FLANGE BREAK-AWAY STEEL SIGNPOST SCHEDULE									
STA	OFFSET	POST	STUB POST 1	SIGN POST 1	STUB POST 2	SIGN POST 2	STRUCTURAL STEEL	CONCRETE	REBAR
	METER		METER				KG	CU M	KG
FAP 310									
31+675	24.58 RT	W10x22	0.914	5.62	0.914	6.2	447	1.8	83.5
31+950	24.06 LT	W10x22	0.914	5.48	0.914	6.02	436	1.8	83.5
32+875	26.68 RT	W10x22	0.914	5.92	0.914	6.45	465	1.8	83.5
33+150	25.0 LT	W10x22	0.914	5.68	0.914	6.33	453	1.8	83.5
FOSTERBURG RD									
65+175	15.37 LT	W8X18	0.762	5.56	0.762	4.99	323	1.1	70.8
SEMINARY RD									
4+825	15.33 RT	W8X18	0.762	5.933	0.762	5.141	337	1.1	70.8
SUB TOTALS			5.18	34.193	5.18	35.131		9.4	475.6
TOTALS			79.684				2462	9.4	475.6

EARTHWORK SCHEDULE		
STATION		FURNISHED EXCAVATION
		CU M
1947+00	TO 1947+50	0.5
1947+50	TO 1947+75	0.9
1947+75	TO 1948+00	3.0
1948+00	TO 1948+25	7.2
1948+25	TO 1948+50	17.5
1948+50	TO 1948+75	13.1
1948+75	TO 1949+00	0.5
30+650	TO 30+675	3.5
30+675	TO 30+700	31.5
30+700	TO 30+725	54.5
30+725	TO 30+742.5	57.2
30+742.5	TO 30+760	84.0
30+760	TO 30+775	77.7
30+775	TO 30+800	63.8
33+987.5	TO 34+000	6.5
34+000	TO 34+012.5	38.1
34+012.5	TO 34+025	69.0
34+025	TO 34+037.5	66.3
34+037.5	TO 34+050	38.1
34+050	TO 34+075	43.8
34+075	TO 34+100	25.3
TOTAL		701.8

IMPACT ATTENUATOR SCHEDULE		
STA	OFFSET	IMPACT ATTENUATOR
		EACH
18+430	RT	3
30+760	LT	3
34+025	RT	3
TOTALS		9

PLOT DATE * DATE *
 FILE NAME * FILE *
 USER NAME * USER *

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES
FAP 310
SECTIONS 60-14-2 & 60-14-2B
MADISON COUNTY

SCALE: VERT. DRAWN BY
 DATE: HORIZ. CHECKED BY