

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	•	MADISON	405	374
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
• SECTION 60-14-2 & 60-14-2B CONTRACT NO. 76986				

PAVING SCHEDULE

LOCATION	STATION	STATION	•PROCESSING MODIFIED SOIL 300MM SQ M	•LIME M TON	AGGREGATE BASE COURSE, TYPE A, 200MM SQ M	BITUMINOUS SURFACE TREATMENT, CLASS A-3				AGGREGATE SHOULDERS TYPE A 150MM SQ M	AGGREGATE SURFACE COURSE, TYPE B, 200MM SQ M	HOT-MIX ASPHALT PAVEMENT, (FULL DEPTH), 190MM SQ M	BITUMINOUS REMOVAL (MISCELLANEOUS) SQ M	HOT-MIX ASPHALT SHOULDERS, 190MM SQ M
						BITUMINOUS MATERIALS (PRIME COAT) 1 APPS M TON	BITUMINOUS MATERIALS (COVER & SEAL COATS) 3 APPS M TON	COVER COAT AGGREGATE 2 APPS M TON	SEAL COAT AGGREGATE 1 APPS M TON					
FRONTAGE ROAD	9+184.782	9+996.645	8325	171					1908		6044			1928
ACCESS ROAD	0+006.000	0+046.983								212				
FOSTERBURG ROAD	65+339.306	65+413.885										298		
TAMM DRIVE	0+004.800	0+087.247			462	0.8	2.4	1.2	0.6	116	85		213	
TOTAL			8325	171	462	0.8	2.4	1.2	0.6	2024	297	6044	511	1928

*NOT A TOTAL QUANTITY

EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION CU M	EARTH • EXCAVATION ADJUSTED FOR SHRINKAGE 25% CU M	EMBANKMENT • CU M	EARTHWORK • BALANCE WASTE(+) OR SHORTAGE (-) CU M	REMARKS
FRONTAGE ROAD					
STA 9+190.000 TO STA 9+997.000	9732.5	7786.0	2213.6	5572.4	
TAMM DRIVE					
STA 0+010.000 TO STA 0+087.000	24.5	19.6	126.4	-106.4	
AGGREGATE ENTRANCE					
STA 0+005.000 TO STA 0+048.000	55.7	44.5	26.5	18.1	QUANTITIES ADJUSTED FOR CURVATURE
SUBTOTAL	9812.7	7850.1	2366.5	5484.1	
FRONTAGE ROAD SUBTOTALS**	9815	7855	2370	5485	

• NOT MEASURED FOR PAYMENT
** NOT A TOTAL QUANTITY

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF QUANTITIES FAP ROUTE 310 FAP ROUTE 310 SECTION 60-14-2, 60-14-2B MADISON COUNTY DRAWN BY BANDY CHECKED BY STEUART DATE
NAME	DATE	