

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	*	MADISON	418	382
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
* SECTION 60-14-2		SECTION 60-14-2B		
CONTRACT NO. 76986				

TEMPORARY EROSION CONTROL SCHEDULE

LOCATION	STATION	LT / RT	TEMPORARY DITCH CHECKS EACH	INLET AND PIPE PROTECTION EACH	EARTH EXCAVATION FOR EROSION CONTROL M TON	PERIMETER EROSION BARRIER METER	AGGREGATE (EROSION CONTROL) M TON
FRONTAGE RD	9+120.000 TO 75+240.000 (WOLF)	RT/LT				129.8	
	9+185.800	LT		1			
	9+220.000 TO 9+275.000	LT				48.5	
	9+225.000 TO 9+260.000	RT				39.1	
	9+230.000	LT	1				
	9+275.000	LT	1				
	9+280.000	RT	1				
	9+320.000	LT	1				
	9+320.000	RT	1				
	9+375.000	RT	1				
	9+390.000	LT	1				
	9+440.000	LT	1				
	9+445.000	RT	1				
	9+453.000	RT			4.5		0.75
	9+457.270	LT		1			
	9+465.000	LT	1				
	9+465.000	RT	1				
	9+474.000	LT	1				
	9+474.000	RT	1				
	9+483.000	LT	1				
	9+483.000	RT	1				
	9+492.000	LT	1				
	9+492.000	RT	1				
	9+500.000	LT	1				
	9+500.000	RT	1				
	9+515.000	RT	1				
	9+523.000	LT	1				
	9+523.000	RT	1				
	9+546.000	LT	1				
	9+546.000	RT	1				
	9+565.000	LT	1				
	9+565.000	RT	1				
	9+592.000	LT	1				
	9+592.000	RT	1				
	9+615.000	LT	1				
	9+615.000	RT	1				
	9+638.000	LT	1				
	9+638.000	RT	1				
	9+661.000	LT	1				
	9+661.000	RT	1				
	9+684.000	LT	1				
	9+684.000	RT	1				
	9+707.000	LT	1				
	9+707.000	RT	1				
	9+730.000	LT	1				
	9+730.000	RT	1				
	9+753.000	LT	1				
	9+753.000	RT	1				
	9+796.000	LT	1				
	9+796.000	RT	1				
	9+842.000	RT	1				
	9+888.000	LT	1				
	9+888.000	RT	1				
	9+934.000	LT	1				
	9+934.000	RT	1				
	9+990.000	LT		1			
WOLF ROAD ENTRANCE	1+025.000	LT			2.7		0.75
ACCESS ROAD	0+029.000	RT	1				
FOSTERBURG RD	65+297.472	LT			10.8		0.60
	65+303.549	LT			10.8		0.60
TAMM DRIVE	0+010.774	LT		1			
	0+013.667 TO 0+080.000	RT				61.7	
STOCKPILE	IL ROUTE 255 AND 143 INTERCHANGE					95	
FRONTAGE ROAD SUBTOTALS*			50	4	29	374	3

* NOT A TOTAL QUANTITY

TEMPORARY SEEDING SCHEDULE

LOCATION	STATION TO STATION	TEMPORARY EROSION CONTROL SEEDING KG
FRONTAGE ROAD	9+087.000 TO 9+996.645	154
WOLF RD ENTRANCE	1+000.000 TO 1+041.083	11
TAMM DRIVE	0+004.800 TO 0+087.247	11
ACCESS ROAD	0+004.800 TO 0+046.983	11
STOCKPILE	IL ROUTE 255 AND 143 INTERCHANGE	21
FRONTAGE ROAD SUBTOTALS*		208

*NOT A TOTAL QUANTITY

EROSION CONTROL BLANKET SCHEDULE

LOCATION	STATION TO STATION	EROSION CONTROL BLANKET SQ M
FRONTAGE ROAD	9+125.000 TO 10+000.000	4429
WOLF RD ENTRANCE	1+000.000 TO 1+041.083	108
TAMM DRIVE	0+000.000 TO 0+087.247	24
ACCESS ROAD	0+000.000 TO 0+047.839	131
TOTAL		4692

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION EROSION AND SEDIMENT CONTROL PLAN
NAME	DATE	
		FAP ROUTE 310 FAP ROUTE 310 SECTION 60-14-2, 60-14-2B MADISON COUNTY DRAWN BY BANDY CHECKED BY STEUART DATE