

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
789		MADISON	42	3
• 125RS-1, 125I-2TS-2				

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	1000 90% FED 10% STATE	1000 90% FED 10% STATE	Y031-IF 90% FED 5% STATE 5% COUNTY	△
* 88040332	SIGNAL HEAD, POLYCARBONATE, LED, 3-FACE, 2-3 SECTION, 1-4 SECTION, BRACKET MOUNTED	EACH	1			1	
20200500	EARTH EXCAVATION (WIDENING)	CU YD	291.4		291.4		
25000200	SEEDING, CLASS 2	ACRE	0.7		0.7		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	63		63		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	63		63		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	63		63		
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	320		320		
35600720	HOT-MIX ASPHALT BASE COURSE WIDENING, 11"	SQ YD	185		185		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	7.04	1.52	5.52		
40600300	AGGREGATE (PRIME COAT)	TON	29.39	7.15	22.24		
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	352.9		352.9		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	976	156	820		
40600990	TEMPORARY RAMP	SQ YD	124	32	92		
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	1224.7	407.2	817.5		
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	12820	4560	8260		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	16		16		
44003100	MEDIAN REMOVAL	SQ FT	10		10		
44004250	PAVED SHOULDER REMOVAL	SQ YD	170		170		
44200176	PAVEMENT PATCHING, TYPE I, 15 INCH	SQ YD	3		3		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	413		413		
48100500	AGGREGATE SHOULDERS, TYPE A 6"	SQ YD	135		135		
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	247		247		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	156		156		
48203100	HOT-MIX ASPHALT SHOULDERS	TON	206.3		206.3		
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	12.5	12.5			
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	3	3			
63200310	GUARDRAIL REMOVAL	FOOT	150	150			
63301210	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	556.25	556.25			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10	4	6		
67100100	MOBILIZATION	L SUM	1	0.5	0.5		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.5	0.5		

* SPECIALTY ITEMS

△ Rev. 4-16-87

PLOT DATE = 1/23/2007
 FILE NAME = I:\2007\125\125RS-1\125I-2TS-2.dgn
 PLOT SCALE = 5/8"=1'-0"
 REFERENCE = #REF#