CONTRACT NO. 76A84

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	60(1,2,3) I	MADISON	10	5
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

PARTIAL DEPTH PATCHING SCHEDULE

BEGIN LOCATION STATION	DRIVING LANE LENGTH (FT.)	PASSING LANE LENGTH (FT.)	LANE WIDTH (FT.)	PARTIAL DEPTH REMOVAL (SQ. YD.)	PARTIAL DEPTH PATCHING (TON)	BITUMINOUS MATERIAL (PRIME COAT) (TON)	AGGREGATE (PRIME COAT) (TON)
NORTHBOUND							
19.000	3448		12	4597.3	514.9	1.44	6.90
19.520		317	12	422.7	47.3	0.13	0.63
19.806	20		12	26.7	3.0	0.01	0.04
19.902	20		12	26.7	3.0	0.01	0.04
20.027		4198	12	5597.3	626.9	1.75	8.40
20.741	723		12	964.0	108.0	0.30	1.45
21.638	20		12	26.7	3.0	0.01	0.04
21.734	20		12	26.7	3.0	0.01	0.04
21.773	20		12	26.7	3.0	0.01	0.04
21.849	20		12	26.7	3.0	0.01	0.04
21.868	20		12	26.7	3.0	0.01	0.04
21.868		20	12	26.7	3.0	0.01	0.04
22.040		20	12	26.7	3.0	0.01	0.04
22.207	20		12	26.7	3.0	0.01	0.04
22.321	20		12	26.7	3.0	0.01	0.04
22.537	20		12	26.7	3.0	0.01	0.04
22.800	40		12	53.3	6.0	0.02	0.08
29.930	20		12	26.7	3.0	0.01	0.04
37.179	243		6	162.0	18.1	0.05	0.24
37.474	100		6	66.7	7.5	0.02	0.10
SOUTHBOUND							
37.150	14		6	9.3	1.0	0.00	0.01
37.120	10		12	13.3	1.5	0.00	0.02
29.590	285		6	190.0	21.3	0.06	0.29
20.542		4958	12	6610.7	740.4	2.07	9.92
20.542	327		12	436.0	48.8	0.14	0.65
20.376	528		12	704.0	78.8	0.22	1.06
20.223	217		12	289.3	32.4	0.09	0.43
19.860	106		12	141.3	15.8	0.04	0.21
15% ANTICIPATED FAILURE				3090.6	346.1	0.97	4.64
TOTAL				23695	2654	7	36

PAVEMENT MARKING SCHEDULE

MILE STA.	LENGTH	THERMOPLASTIC 8" SOLID WHITE	THERMOPLASTIC 4" SOLID YELLOW	THERMOPLASTIC 4" SOLID WHITE	THERMOPLASTIC 4" SKIP DASH WHITE	RPMS	RPM REMOVAL
NORTHBOUND							
19.000	3448			3448	862	45	45
19.520	317		317		79		
20.027	4198		4198		1050		
20.741	723			723	181	19	19
37.179	243	243				6	6
37.474	100	100				3	3
SOUTHBOUND							
29.590	285	285				7	7
20.542	4958		4958		1240		
20.542	327			327	82	8	8
20.376	528			528	132	13	13
20.223	217			217	54	6	6
19.860	106			106	27	3	3
ADD 15%		94	1421	802	556		
TOTAL		722	10894	6151	4263	110	110
PAY ITEM TOTAL		722		21308		110	110

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

FAI ROUTE 55
SECTION 60-(1,2,3) I
MADISON COUNTY

SCALE: VERT. HORIZ.
DATE
DRAWN BY
CHECKED BY

PLOT DATE = 2/14/2007
FILE NAME = c:\pw_work\ildot\d95687\plan\pb95687v.dgn
PLOT SCALE = 100.0024 ' / IN.
REFERENCE = $REF4