

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	60(1,2,3) I	MADISON	10	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CLASS B PAVEMENT PATCHING SCHEDULE

BEGIN LOCATION STATION	DRIVING LANE LENGTH (FT.)	PASSING LANE LENGTH (FT.)	LANE WIDTH (FT.)	TYPE II PATCH (SQ. YD.)	TYPE III PATCH (SQ. YD.)	TYPE IV PATCH (SQ. YD.)	DOWEL BARS (EACH)	SAW CUTS (FT.)	PAVEMENT FABRIC (SQ. YD.)
NORTHBOUND									
19.116	15		12		20.0		20	66	20.0
19.307	15		12		20.0		20	66	20.0
19.462	10		12	13.3			20	56	
19.480	12		12		16.0		20	60	16.0
19.806	20		12				20	76	
19.863	12		12		16.0		20	60	16.0
19.902	20		12				20	76	
19.940	9		12	12.0			20	54	
21.081	10		12	13.3			20	56	
21.831	12		12		16.0		20	60	16.0
21.983	10		12	13.3			20	56	
22.002	10		12	13.3			20	56	
22.022	15		12		20.0		20	66	20.0
22.040	10		12	13.3			20	56	
22.225	10		12	13.3			20	56	
22.244	12		12		16.0		20	60	16.0
22.263	15		12		20.0		20	66	20.0
22.282	8		12	10.7			20	52	
22.302	8		12	10.7			20	52	
22.426	20		12			26.7	20	76	26.7
22.454	8		12	10.7			20	52	
22.470	9		12	12.0			20	54	
22.520	10		12	13.3			20	56	
22.537	20		12				20	76	
22.613	15		12		20.0		20	66	20.0
22.818	15		12		20.0		20	66	20.0
22.837	10		12	13.3			20	56	
22.856	10		12	13.3			20	56	
23.011	10		12	13.3			20	56	
23.030	10		12	13.3			20	56	
23.030		20	12			26.7	20	36	26.7
23.049	8		12	10.7			20	52	
23.049		20	12			26.7	20	36	26.7
23.078	8		12	10.7			20	52	
23.106	8		12	10.7			20	52	
23.279	8		12	10.7			20	52	
23.570	6		12	8.0			20	48	
23.585	9		12	12.0			20	54	
23.604	9		12	12.0			20	54	
23.643	8		12	10.7			20	52	
23.758	8		12	10.7			20	52	
23.777	8		12	10.7			20	52	
23.796	10		12	13.3			20	56	
23.064	8		12	10.7			20	52	
24.294	9		12	12.0			20	54	
24.313	8		12	10.7			20	52	
24.332	10		12	13.3			20	56	
24.371	9		12	12.0			20	54	
24.485	8		12	10.7			20	52	
24.765	9		12	12.0			20	54	
24.919	9		12	12.0			20	54	
24.938	8		12	10.7			20	52	
25.014	9		12	12.0			20	54	
25.032	9		12	12.0			20	54	
25.052	8		12	10.7			20	52	

CLASS B PAVEMENT PATCHING SCHEDULE - CONTINUED

BEGIN LOCATION STATION	DRIVING LANE LENGTH (FT.)	PASSING LANE LENGTH (FT.)	LANE WIDTH (FT.)	TYPE II PATCH (SQ. YD.)	TYPE III PATCH (SQ. YD.)	TYPE IV PATCH (SQ. YD.)	DOWEL BARS (EACH)	SAW CUTS (FT.)	PAVEMENT FABRIC (SQ. YD.)
NORTHBOUND									
25.091	8		12	10.7			20	52	
25.354	8		12	10.7			20	52	
25.526	15		12		20.0		20	66	20.0
25.564	8		12	10.7			20	52	
28.350	10		12	13.3			20	56	
28.377	10		12	13.3			20	56	
28.531	10		12	13.3			20	56	
30.999	12		12		16.0		20	60	16.0
31.293	10		12	13.3			20	56	
31.491	9		12	12.0			20	54	
32.012	10		12	13.3			20	56	
32.069	10		12	13.3			20	56	
32.088	9		12	12.0			20	54	
32.933	8		12	10.7			20	52	
33.106	9		12	12.0			20	54	
33.886	13		12		17.3		20	62	17.3
33.906	13		12		17.3		20	62	17.3
33.921	12		12		16.0		20	60	16.0
34.844		11	12	14.7			20	36	
SOUTHBOUND									
37.214	20		12			26.7	20	76	26.7
34.785	6		12	8.0			20	48	
33.552	15		12		20.0		20	66	20.0
32.491	9		12	12.0			20	54	
32.280	8		12	10.7			20	52	
32.223	15		12		20.0		20	66	20.0
32.050	10		12	13.3			20	56	
32.031	12		12		16.0		20	60	16.0
31.897	8		12	10.7			20	52	
31.609	8		12	10.7			20	52	
31.379	8		12	10.7			20	52	
31.360	7		12	9.3			20	50	
31.275	10		12	13.3			20	56	
31.010	12		12		16.0		20	60	16.0
30.223	10		12	13.3			20	56	
29.993	10		12	13.3			20	56	
29.685	6		12	8.0			20	48	
29.666	6		12	8.0			20	48	
29.576	12		12		16.0		20	60	16.0
28.889	8		12	10.7			20	52	
28.630	10		12	13.3			20	56	
28.587	7		12	9.3			20	50	
28.568	8		12	10.7			20	52	
28.549	8		12	10.7			20	52	
27.990	7		12	9.3			20	50	
27.970	7		12	9.3			20	50	

PLOT DATE = 2/14/2007
 FILE NAME = c:\projects\76a94\plan\p10.dwg
 REFERENCE = 0000

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULES OF QUANTITIES
 FAI ROUTE 55
 SECTION 60-(1,2,3) I
 MADISON COUNTY

SCALE: VERT. _____
 HORIZ. _____
 DATE _____

DRAWN BY _____
 CHECKED BY _____