

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	60-(1,2,3) I	MADISON	10	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

CLASS B PAVEMENT PATCHING SCHEDULE CONTINUED

BEGIN LOCATION STATION	DRIVING LANE LENGTH (FT.)	PASSING LANE LENGTH (FT.)	LANE WIDTH (FT.)	TYPE II PATCH (SQ. YD.)	TYPE III PATCH (SQ. YD.)	TYPE IV PATCH (SQ. YD.)	DOWEL BARS (EACH)	SAW CUTS (FT.)	PAVEMENT FABRIC (SQ. YD.)
SOUTHBOUND									
27.952	13		12		17.3		20	62	17.3
27.825	15		12		20.0		20	66	20.0
27.681	6		12	8.0			20	48	
27.663	8		12	10.7			20	52	
27.585	15		12		20.0		20	66	20.0
27.509	10		12	13.3			20	56	
27.360	8		12	10.7			20	52	
27.337	8		12	10.7			20	52	
27.318	7		12	9.3			20	50	
27.280	8		12	10.7			20	52	
27.060	8		12	10.7			20	52	
27.036	8		12	10.7			20	52	
26.283	8		12	10.7			20	52	
25.996	8		12	10.7			20	52	
25.785	8		12	10.7			20	52	
25.535	8		12	10.7			20	52	
25.516	7		12	9.3			20	50	
25.314	7		12	9.3			20	50	
25.305	9		12	12.0			20	54	
25.286	8		12	10.7			20	52	
25.135	7		12	9.3			20	50	
25.020	8		12	10.7			20	52	
24.828	9		12	12.0			20	54	
24.808	8		12	10.7			20	52	
24.790	8		12	10.7			20	52	
24.456	7		12	9.3			20	50	
24.404	9		12	12.0			20	54	
24.385	8		12	10.7			20	52	
24.365	8		12	10.7			20	52	
24.119	8		12	10.7			20	52	
24.100	8		12	10.7			20	52	
23.907	9		12	12.0			20	54	

CLASS B PAVEMENT PATCHING SCHEDULE CONTINUED

BEGIN LOCATION STATION	DRIVING LANE LENGTH (FT.)	PASSING LANE LENGTH (FT.)	LANE WIDTH (FT.)	TYPE II PATCH (SQ. YD.)	TYPE III PATCH (SQ. YD.)	TYPE IV PATCH (SQ. YD.)	DOWEL BARS (EACH)	SAW CUTS (FT.)	PAVEMENT FABRIC (SQ. YD.)
SOUTHBOUND									
23.775	13		12		17.3		20	62	17.3
23.331	15		12		20.0		20	66	20.0
23.235	15		12		20.0		20	66	20.0
23.176	15		12		20.0		20	66	20.0
22.986	8		12	10.7			20	52	
22.966	8		12	10.7			20	52	
22.948	8		12	10.7			20	52	
22.929	10		12	13.3			20	56	
22.910	8		12	10.7			20	52	
22.891	8		12	10.7			20	52	
22.487	8		12	10.7			20	52	
22.200	8		12	10.7			20	52	
22.182	8		12	10.7			20	52	
22.128	8		12	10.7			20	52	
22.090	8		12	10.7			20	52	
21.974	10		12	13.3			20	56	
21.917	12		12		16.0		20	60	16.0
21.898	8		12	10.7			20	52	
21.879	8		12	10.7			20	52	
21.821	8		12	10.7			20	52	
21.665	8		12	10.7			20	52	
21.647	8		12	10.7			20	52	
21.628	8		12	10.7			20	52	
21.608	8		12	10.7			20	52	
21.358	8		12	10.7			20	52	
21.339	10		12	13.3			20	56	
21.320	9		12	12.0			20	54	
21.301	6		12	8.0			20	48	
19.542	9		12	12.0			20	54	
19.523	10		12	13.3			20	56	
15% ANTICIPATED FAILURE				215.20	76.40	16.00	486.00	1338.90	92.4
TOTAL				1650	586	123	3726	10265	708

PLOT DATE: 2/14/2007
 FILE NAME: C:\projects\76A84\76A84.dwg
 PLOTTER: HP DesignJet 5000
 REFERENCE: 48874

REVISIONS		DATE
NAME		

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULES OF QUANTITIES
 FAI ROUTE 55
 SECTION 60-(1,2,3) I
 MADISON COUNTY

SCALE: VERT. _____
 HORIZ. _____
 DATE _____

DRAWN BY _____
 CHECKED BY _____