FAP. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1215	99-00169-05-WR	LAKE	153	64
CONSTRUCTION DETAIL				
CONTRACT NO. 83847	ILLINOIS	SUNSET AVENUE		

NOTE:
ALL ELEVATIONS REPRESENT PROPOSED TOP OF THE FINAL SURFACE COURSE. ALL STATION AND OFFSET INFORMATION IS FROM THE CONSTRUCTION CENTERLINE OF SUNSET AVENUE.

PLAN
NOTE BOOK
NO.
SURVEYED
PLOTTED
CHARTS CHECKED
ALIGNMENT CHECKED
RT. OF WAY CHECKED
BY
DATE

PROFILE
NOTE BOOK
NO.
SURVEYED
PLOTTED
CHARTS CHECKED
S. M.'S NOTED
STRUCTURE NOTATIONS CHECKED
BY
DATE

46+00.00
CONST ℄
726.86

46+00

EXISTING ROW

46+82.49
40.00′ RT
726.26

CENTER PT
46+56.15
70.00′ RT

PC46+95.92
68.91′ RT
726.03

46+95.95
70.00′ RT
726.02
LOW PT

46+94.68
60.00′ RT
726.09

46+90.63
50.00′ RT
726.17

46+96.20
80.00′ RT
726.12

R=40′

PC46+56.15
30.00′ RT
726.48

46+50.00
CONST ℄
727.05

CONSTRUCTION ℄

46+82.49
30.00′ RT
726.63

46+97.27
122.23′ RT
726.35

46+96.38
87.24′ RT
726.19

47+12.09
121.84′ RT
726.52

47+10.97
86.86′ RT
726.35

BUTT JOINT

47+26.92
121.47′ RT
726.34

47+26.14
86.48′ RT
726.21

47+10.97
80.00′ RT
726.28

47+10.97
70.00′ RT
726.17

47+10.97
60.00′ RT
726.32

47+10.97
50.00′ RT
726.48

47+10.97
40.00′ RT
726.63

47+00.00
CONST ℄
727.32

47+10.97
30.00′ RT
726.79

47+00

TRANSITION
TO B-6.12
CURB IN 25′

47+25.99
80.00′ RT
726.17

PC47+25.79
70.84′ RT
726.12

47+25.78
70.00′ RT
726.11
LOW PT

47+31.08
50.00′ RT
726.45

47+27.02
60.00′ RT
726.28

CENTER PT
47+65.56
70.00′ RT

R=40′

47+39.21
30.00′ RT
726.95

47+50.00
CONST ℄
727.61

SUNSET AVENUE

47+39.21
40.00′ RT
726.67

EXISTING ROW

PC47+65.56
30.00′ RT
727.13

48+00.00
CONST ℄
728.00

48+00

EXISTING ROW

46+76.90
40.00′ LT
726.30

46+85.13
50.00′ LT
726.23

CENTER PT
46+50.33
70.00′ LT

PC46+50.33
30.00′ LT
726.45

46+89.26
60.00′ LT
726.18

46+90.55
70.00′ LT
726.11

R=40′

46+76.90
30.00′ LT
726.60

PC46+90.49
72.17′ LT
726.09

46+88.63
107.12′ LT
725.67

47+07.35
73.17′ LT
726.13

47+05.29
108.11′ LT
725.96

ERNIE KRUGER CIRCLE

BUTT JOINT

47+07.35
30.00′ LT
726.77

47+07.35
40.00′ LT
726.69

47+07.35
50.00′ LT
726.60

47+07.35
60.00′ LT
726.40

47+07.35
70.00′ LT
726.20

47+23.80
74.13′ LT
726.08

47+21.95
109.08′ LT
725.67

TRANSITION
TO B-6.12
CURB IN 25′

47+24.02
70.00′ LT
726.13

PC47+24.13
67.96′ LT
726.15

47+37.72
30.00′ LT
726.94

47+50.00
30.00′ LT
727.01

47+29.49
50.00′ LT
726.37

47+25.37
60.00′ LT
726.25

R=40′

47+37.72
40.00′ LT
726.53

CENTER PT
47+64.30
70.00′ LT

PC47+64.30
30.00′ LT
727.12

EXISTING ROW

47+50.00
32.62′ LT
726.88

INTERSECTION DETAIL
ERNIE KRUGER CIRCLE

10 0 10 20
SCALE IN FEET

REVISIONS	
NAME	DATE

LakeCounty
Division of Transportation

SUNSET AVENUE

INTERSECTION DETAIL