

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	05-00130-00-BR	WILL	41	3
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 83889

Item No.	Items	Unit	Quantity
20200100	EARTH EXCAVATION	CU YD	70
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1,468
20400800	FURNISHED EXCAVATION	CU YD	1,505
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	903
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	376
20800150	TRENCH BACKFILL	CU YD	307
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	3,210
21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	4,215
21301072	EXPLORATION TRENCH, 72" DEPTH	FOOT	40
25000210	SEEDING, CLASS 2A	ACRE	0.9
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	78
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	78
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	78
25100630	EROSION CONTROL BLANKET	SQ YD	3,310
28000400	PERIMETER EROSION BARRIER	FOOT	4000
28000720	MULCH, METHOD 2	ACRE	0.9
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	1,300
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	1,435
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	680
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	181
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	339
42400440	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH, SPECIAL	SQ FT	4,499
44000100	PAVEMENT REMOVAL	SQ YD	1,454
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	136
50200100	STRUCTURE EXCAVATION	CU YD	1144.2
50300225	CONCRETE STRUCTURES	CU YD	166
50300285	FORM LINER TEXTURED SURFACE	SQ FT	614.0
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	3,376
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	32,940
50901720	BICYCLE RAILING	FOOT	507
51201600	FURNISHING STEEL PILES HP12X53	FOOT	1,326
51202305	DRIVING PILES	FOOT	1,326
51203600	TEST PILE STEEL HP12X53	EACH	6
51204650	PILE SHOES	EACH	36
51500100	NAME PLATE	EACH	1
542A1057	PIPE CULVERTS, CLASS A, TYPE 2 12"	FOOT	78
54200430	PIPE CULVERTS, TYPE 1 RCCP 15"	FOOT	101
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1
* 56100600	WATER MAIN 6"	FOOT	10
* 56100900	WATER MAIN 12"	FOOT	10
* 56101000	WATER MAIN 16"	FOOT	117
* 56105200	WATER VALVES 12"	EACH	1
* 56105300	WATER VALVES 16"	EACH	1
* 56400100	FIRE HYDRANT TO BE MOVED	EACH	1

Item No.	Items	Unit	Quantity
58700300	CONCRETE SEALER	SQ FT	2,817
60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	4
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	1
60248900	VALVE VAULTS, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2
60266500	VALVE VAULTS TO BE REMOVED	EACH	2
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	5
67100100	MOBILIZATION	L SUM	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1
72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	1
72900100	METAL POST - TYPE A	FOOT	15
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2,040
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1
* 81100200	CONDUIT ATTACHED TO STRUCTURE, 3/4" DIA., GALVANIZED STEEL	FOOT	610
* 81300100	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 4" X 4" X 3"	EACH	2
* 81300320	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 8" X 8" X 6"	EACH	2
* 81603015	UNIT DUCT, 600V, 3-1C #10, 1/C #8 GROUND,(XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	204
* 81700315	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 3-1/C NO. 10	FOOT	610
* 82103250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 250 WATT	EACH	2
* 83012100	LIGHT POLE, ALUMINUM, 30 FT. M.H., TENON MOUNT	EACH	2
* 83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	24
* X0323842	WATER MAIN LINE STOP 12"	EACH	1
X0322939	RELOCATE EXISTING FLARED END SECTION	EACH	2
* X0323174	DUCTILE IRON WATER MAIN BEND, 45 DEGREE, 16 INCHES	EACH	2
* X0323191	DUCTILE IRON WATER MAIN TEE, 16" X 6"	EACH	1
* X0323192	DUCTILE IRON WATER MAIN TEE, 16" X 12"	EACH	1
* XX002161	ABANDON EXISTING WATER MAIN	EACH	1
XX002202	VEHICLE CONTROL BOLLARDS	EACH	3
XX001910	PRECAST BLOCK RETAINING WALL	SQ FT	115
* XX004056	MECHANICALLY STABILIZED EARTH RETAINING WALL	SQ FT	5,308
* X0322508	PEDESTRIAN TRUSS SUPERSTRUCTURE	SQ FT	8,410
* X0325207	TELEVISION INSPECTION OF SEWER	FOOT	2,400
Δ Z0076600	TRAINEES	HOUR	500
* XX006788	WATER MAIN LINE STOP 16"	EACH	1
* XX006789	DUCTILE IRON WATER MAIN BEND, 90 DEGREE, 16 INCHES	EACH	2

\* SPECIALTY ITEMS  
Δ Y080

REVISIONS	
NAME	DATE

**URS** 100 S. WACKER DR., STE 500 TEL (312) 939-1000  
CHICAGO IL, 60606 FAX (312) 939-4198

CITY OF NAPERVILLE

SUMMARY OF QUANTITIES

NONE

50' 0 50' 100'

DATE : 12-8-2006

DRAWN BY : DGM  
CHECKED BY : DDL