F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1394	97-00226-00-FP	COOK	80	13
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO.: 83898

PERMANENT PAVEMENT MARKING

STATION FROM	STATION TO	OFFSET	LOCATION	TYPE (SOLID, SKIP-DASH, ETC.)	COLOR	78000200 THERMO. PAVEMENT MARKING - LINE 4"	78000400 THERMO. PAVEMENT MARKING - LINE 6"	78000600 THERMO. PAVEMENT MARKING - LINE 12"	78000650 THERMO. PAVEMENT MARKING - LINE 24"
00+81	01+76	7.7	LT	SOLID	WHITE		94		
00+81	02+94	4.3	RT	SOLID	YELLOW	70			
01+76	02+94	7.7	LT	DOTTED	WHITE		120		
02+95	04+04		CENTERLINE	SKIP-DASH	YELLOW	28			
04+22	04+37	38.2	LT	SOLID	WHITE				15
04+22	04+51	27.5	LT	SOLID	WHITE		29		
04+22	04+51	33.5	LT	SOLID	WHITE		29		
04+22	04+51	26.6	RT	SOLID	WHITE		29		
04+22	04+51	32.6	RT	SOLID	WHITE		29		
04+69	08+19		CENTERLINE	SKIP-DASH	YELLOW	110			
08+27	08+30	5.0	RT	SOLID	WHITE	7			
08+39	08+51	37.2	LT	SOLID	WHITE				13
08+39	08+63	26.9	LT	SOLID	WHITE		25		
08+39	08+63	32.9	LT	SOLID	WHITE		25		
08+39	08+63	27.1	RT	SOLID	WHITE		25		
08+39	08+63	33.1	RT	SOLID	WHITE		25		
08+51	08+63	36.2	RT	SOLID	WHITE				13
08+83	12+33		CENTERLINE	SKIP-DASH	YELLOW	110			
12+49	12+63	36.4	LT	SOLID	WHITE				15
12+49	12+79	26.9	LT	SOLID	WHITE		29		
12+49	12+79	32.9	LT	SOLID	WHITE		29		
12+49	12+79	27.1	RT	SOLID	WHITE		29		
12+49	12+79	33.1	RT	SOLID	WHITE		29		
12+65	12+79	37.7	RT	SOLID	WHITE				15
12+94	16+57		CENTERLINE	SKIP-DASH	YELLOW	110			
16+77	17+06	27.0	RT	SOLID	WHITE		29		
16+77	17+06	33.0	RT	SOLID	WHITE		29		
16+82	16+85	11.0	RT	SOLID	WHITE	7			
17+25	19+30		CENTERLINE	SKIP-DASH	YELLOW	70			
19+30	20+31		CENTERLINE	SOLID	YELLOW	101			
20+29	20+31		RT	SOLID	WHITE				15
20+29	20+63		CROSSWALK	SOLID	WHITE		29		
20+50	20+71		CROSSWALK	SOLID	WHITE		29		
20+56	21+09	26.4	RT	SOLID	WHITE		29		
20+80	21+09	32.4	RT	SOLID	WHITE		29		
20+80	21+09	37.4	RT	SOLID	WHITE				15
20+95	21+36		CROSSWALK	SOLID	WHITE		32		
21+18	21+36			SOLID	WHITE				
21+28	21+46		CROSSWALK	SOLID	WHITE		32		
21+57	21+59		LT	SOLID	WHITE				15
21+57	22+59		CENTERLINE	SOLID	WHITE	204			
22+59	24+81		CENTERLINE	SKIP-DASH	YELLOW	70			
22+99	23+14	37.7	LT	SOLID	YELLOW				
22+99	23+28	27.0	LT	SOLID	WHITE		29		
22+99	23+28	33.0	LT	SOLID	WHITE		29		
23+00	23+29	26.9	RT	SOLID	WHITE		29		
23+00	23+29	32.9	RT	SOLID	WHITE		29		
23+14	23+29	38.1	RT	SOLID	WHITE				15
23+35	23+38	6.4	RT	SOLID	WHITE	7			
23+45	27+00		CENTERLINE	SKIP-DASH	YELLOW	110			
27+00	28+02	0.0	RT	DOTTED	WHITE		104		
27+00	28+75	0.0	LT	SOLID	YELLOW	350			
28+02	28+75	7.5	RT	SOLID	WHITE		71		
29+67	31+21		CENTERLINE	SOLID	YELLOW	154			
31+21	32+21		CENTERLINE	SKIP-DASH	YELLOW	40			
32+85	35+48		CENTERLINE	SKIP-DASH	YELLOW	80			
36+26	38+82		CENTERLINE	SKIP-DASH	YELLOW	80			
38+82	38+88		CENTERLINE	SOLID	WHITE				34
39+00	39+15	35.2	LT	SOLID	WHITE				15
39+00	39+29	27.0	LT	SOLID	WHITE		29		
39+00	39+29	33.0	LT	SOLID	WHITE		29		
39+00	39+29	26.3	RT	SOLID	WHITE		29		
39+00	39+29	32.3	RT	SOLID	WHITE		29		
39+15	39+29	35.3	RT	SOLID	WHITE				15
39+41	39+47		CROSSWALK	SOLID	WHITE				34
39+47	42+14		CENTERLINE	SKIP-DASH	YELLOW	80			
39+80	46+49		CENTERLINE	SKIP-DASH	YELLOW	200			
46+49			CROSSWALK	SOLID	WHITE		29		
46+55			CROSSWALK	SOLID	WHITE		29		
46+74	46+88	34.1	LT	SOLID	WHITE				15
46+74	47+03	26.7	LT	SOLID	WHITE		29		
46+74	47+03	32.7	LT	SOLID	WHITE		29		
46+74	47+03	27.1	RT	SOLID	WHITE		29		
46+74	47+03	33.1	RT	SOLID	WHITE		29		
47+09	47+12	5.6	RT	SOLID	WHITE	7			

PERMANENT PAVEMENT MARKING

STATION FROM	STATION TO	OFFSET	LOCATION	TYPE (SOLID, SKIP-DASH, ETC.)	COLOR	78000200 THERMO. PAVEMENT MARKING - LINE 4"	78000400 THERMO. PAVEMENT MARKING - LINE 6"	78000600 THERMO. PAVEMENT MARKING - LINE 12"	78000650 THERMO. PAVEMENT MARKING - LINE 24"
47+22			CROSSWALK	SOLID	WHITE		29		
47+28			CROSSWALK	SOLID	WHITE		29		
47+28	50+91		CENTERLINE	SKIP-DASH	YELLOW	110			
51+79	55+88		CENTERLINE	SOLID	YELLOW	824			
55+86	55+88		RT	SOLID	WHITE				16
55+94	55+98		CROSSWALK	SOLID	WHITE		40		
56+01	56+03		CROSSWALK	SOLID	WHITE		46		
56+01	56+65	24.0	RT	SOLID	WHITE		64		
56+77	56+79		LT	SOLID	WHITE				20
56+77	58+17	3.4	LT	SOLID	YELLOW	300			
56+79	57+29	15.3	LT	SOLID	WHITE		50		
56+79	57+54	6.0	RT	DOTTED	WHITE	20			
57+29	58+15	15.3	LT	DOTTED	WHITE	22			
57+54	58+15	6.0	RT	SOLID	WHITE		59		
58+15	58+17		RT	SOLID	WHITE				20
58+16	58+65	27.6	LT	SOLID	WHITE		49		
58+16	58+70	33.6	LT	SOLID	WHITE		54		
58+70	58+80		CROSSWALK	SOLID	WHITE		46		
58+70	58+84		CROSSWALK	SOLID	WHITE		46		
58+84	58+86		LT	SOLID	WHITE				17
58+84	58+96		CENTERLINE	SOLID	YELLOW	24			
59+32	60+09		CENTERLINE	SOLID	YELLOW	154			
60+09	62+03		CENTERLINE	SKIP-DASH	YELLOW	60			
62+21	62+36	37.7	LT	SOLID	WHITE				15
62+21	62+50	27.4	LT	SOLID	WHITE		29		
62+21	62+50	33.4	LT	SOLID	WHITE		29		
62+27	62+56	24.9	RT	SOLID	WHITE		31		
62+27	62+56	30.9	RT	SOLID	WHITE		30		
62+41	62+56	35.4	RT	SOLID	WHITE				15
62+69	65+41		CENTERLINE	SKIP-DASH	YELLOW	80			
65+53	65+83	27.0	LT	SOLID	WHITE		30		
65+53	65+83	33.0	LT	SOLID	WHITE		30		
65+58	65+86	26.6	RT	SOLID	WHITE		29		
65+58	65+86	32.6	RT	SOLID	WHITE		29		
66+00	68+67		CENTERLINE	SKIP-DASH	YELLOW	80			
68+74	68+78	5.5	RT	SOLID	WHITE	7			
68+85	69+14	27.0	LT	SOLID	WHITE		29		
68+85	69+14	33.0	LT	SOLID	WHITE		29		
68+92	69+16	267.0	RT	SOLID	WHITE		29		
68+92	69+16	32.7	RT	SOLID	WHITE		29		
69+04	69+16	35.5	RT	SOLID	WHITE				15
69+33	72+00		CENTERLINE	SKIP-DASH	YELLOW	80			
72+17	72+32	34.6	LT	SOLID	WHITE				15
72+17	72+45	27.0	LT	SOLID	WHITE		29		
72+17	72+45	33.0	LT	SOLID	WHITE		29		
72+19	72+46	26.7	RT	SOLID	WHITE		29		
72+19	72+46	32.7	RT	SOLID	WHITE		29		
72+33	72+46	36.0	RT	SOLID	WHITE				15
72+60	72+61		CROSSWALK	SOLID	WHITE		29		
72+66	72+67		CROSSWALK	SOLID	WHITE		29		
72+67	79+72		CENTERLINE	SKIP-DASH	YELLOW	190			
75+51	75+65	34.7	LT	SOLID	WHITE				15
75+51	75+79	26.9	LT	SOLID	WHITE		29		
75+51	75+79	32.9	LT	SOLID	WHITE		29		
75+81	75+85	6.1	RT	SOLID	WHITE	7			
78+83	78+97	36.9	LT	SOLID	WHITE				15
78+83	79+11	27.1	LT	SOLID	WHITE		28		
78+83	79+11	33.1	LT	SOLID	WHITE		28		
79+12	79+16	9.6	RT	SOLID	WHITE	7			
79+72	81+91	0.0	RT	SKIP-DASH	WHITE		120		
79+72	82+88	0.0	LT	SOLID	YELLOW	428			
81+91	82+86	5.7	RT	SOLID	WHITE		94		
82+86	82+88		RT	SOLID	WHITE				24
SUBTOTALS						2,393	1,367	0	202

STRAND ASSOCIATES, INC.® ENGINEERS

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

FAU 1394
DIVISION STREET

SCHEDULE OF QUANTITIES

SCALE: VERT.
HORIZ.
DATE 1/25/2007

DRAWN BY JBH
CHECKED BY JDM

FILENAME: S:\Jobs\754-8887\Civil\Sheets\Sheet Files\Elements\Schedule of Quantities-Division.dgn
DATE: 1/25/2007
TIME: 2:49:11 PM