CONTRACT NO.: 83904

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2638	00-00139-00-RS	DUPAGE	68	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

PROJECT NO.: M-8003 (663)

SUMMARY OF QUANTITIES

SP	CODED PAY ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 1000-2A		TRAFFIC SIGNALS Y031-1F	
					PARTICIPATING	NON-PARTICIPATING	PARTICIPATING	NON-PARTICIPATING
	20101000	TEMPORARY FENCE	FOOT	2,000	2,000	-	-	-
	20200100	EARTH EXCAVATION	CU YD	182	182	-	-	-
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	680	680	-	-	-
	20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	484	484	-	-	-
	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	1,452	1,452	-	-	-
*	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1,696	1,696	-	-	-
*	25200200	SUPPLEMENTAL WATERING	UNIT	26	26	-	-	-
*	25200700	SODDING, SPECIAL	SQ YD	1,696	1,696	-	-	-
	31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	3,300	3,300	-	-	-
	40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	130	130	-	-	-
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	11,610	11,610	-	-	-
	40600300	AGGREGATE (PRIME COAT)	TON	232	232	-	-	-
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	422	422	-	-	-
	40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	8,416	8,416	-	-	-
	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	5,611	5,611	-	-	-
	42001300	PROTECTIVE COAT	SQ YD	4,241	4,241	-	-	-
	42300710	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH, SPECIAL	SQ YD	145	145	-	-	-
	42300800	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH, SPECIAL	SQ YD	95	95	-	-	-
	42400430	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH, SPECIAL	SQ FT	25,493	25,493	-	-	-
	42400800	DETECTABLE WARNING	SQ FT	728	728	-	-	-
	44000165	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	SQ YD	57,245	57,245	-	-	-
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	953	953	-	-	-
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	6,306	6,306	-	-	-
	44000600	SIDEWALK REMOVAL	SQ FT	23,280	23,280	-	-	-
	44201335	CLASS C PATCHES, TYPE IV, 8 INCH	SQ YD	1,145	1,145	-	-	-
	44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	5,725	5,725	-	-	-
	44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	57,245	57,245	-	-	-
	60255800	MANHOLES TO BE ADJUSTED W/ NEW TYPE 1 FRAME, CLOSED LID	EACH	4	4	-	-	-
	60258200	MANHOLES TO BE RECONSTRUCTED W/ NEW TYPE 1 FRAME, CLOSED LID	EACH	2	2	-	-	-
	60260500	INLETS TO BE ADJUSTED WITH NEW TYPE 3 FRAME & GRATE	EACH	5	5	-	-	-
	60265900	VALVE VAULTS TO BE ADJUSTED W/ NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1	-	-	-
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	6,288	6,288	-	-	-
	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	69	69	-	-	-
	67100100	MOBILIZATION	L SUM	1	1	-	-	-
	70102620	TRAFFIC CONTROL AND PROTECTION, SECTION 701501	L SUM	1	1	-	-	-
	70102635	TRAFFIC CONTROL AND PROTECTION, SECTION 701701	L SUM	1	1	-	-	-
	70102640	TRAFFIC CONTROL AND PROTECTION, SECTION 701801	L SUM	1	1	-	-	-
	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	51,092	51,092	-	-	-
*	78003100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS	SQ FT	503	503	-	-	-
*	78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	26,672	26,672	-	-	-
*	78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	5,796	5,796	-	-	-
*	78003150	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 12"	FOOT	485	485	-	-	-
*	78003180	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 24"	FOOT	1,074	1,074	-	-	-
*	81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	25	-	-	-	25
*	81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	1,213	-	-	-	1,213
*	81100600	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	10	-	-	-	10
*	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	8	-	-	-	8
*	86000100	MASTER CONTROLLER	EACH	1	-	-	-	1
*	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 3C	FOOT	1,658	-	-	-	1,658
*	87301615	ELECTRIC CABLE IN CONDUIT, COMMUNICATION, NO. 16 6 PAIR	FOOT	4,004	-	-	-	4,004
*	87900200	DRILL EXISTING HANDHOLE	EACH	34	-	-	-	34
*	88102710	PEDESTRIAN SIGNAL HEAD, L.E.D., 1-FACE, BRACKET MOUNTED	EACH	44	-	-	-	44
*	88102717	PEDESTRIAN SIGNAL HEAD, L.E.D., 1-FACE, BRACKET MOUNTED, COUNTDOWN TIMER	EACH	8	-	-	-	8

* INDICATES SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

VILLAGE OF LOMBARD
WESTMORE /MEYERS RESURFACING PROJECT

SUMMARY OF QUANTITIES
SHEET 1 OF 2

SCALE: NTS
DATE: 01/31/07
DRAWN BY: JMT
CHECKED BY: JMT

PLOT DATE = $DATE$
FILE NAME = $FILEN$