

SCHEDULES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5565	06-00127-00-FP	WHITESIDE	24	5
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

DETECTABLE WARNINGS		
STATION	SO FT	REMARKS
RT 51+80	6	3'X2'
LT 51+82	6	3'X2'
RT 56+38	6	3'X2'
RT 56+81.5	6	3'X2'
RT 64+67	6	3'X2'
LT 65+14	6	3'X2'
RT 65+16	6	3'X2'
LT 69+02.5	6	3'X2'
RT 69+02.5	6	3'X2'
PROJECT TOTAL	54	

42400800

STORM SEWERS, CLASS A, TYPE 1 12"		
STATION	FOOT	REMARKS
59+50	46	ACROSS 19TH ST
64+50	46	ACROSS 19TH ST
LT 67+50	4	BETWEEN MANHOLE AND INLET
PROJECT TOTAL	96	

550A0050

STORM SEWERS, CLASS A, TYPE 1 15"		
STATION	FOOT	REMARKS
RT 65+28.28 TO 67+17.73	184	BETWEEN INLET AND MANHOLE
RT 67+17.73 TO 67+50	28	BETWEEN MANHOLE AND INLET
PROJECT TOTAL	212	

550A0070

STORM SEWERS, CLASS A, TYPE 1 18"		
STATION	FOOT	REMARKS
RT 51+74.64 TO 53+50	172	MANHOLE TO INLET
RT 53+50 TO 57+00	344	INLET TO INLET
RT 57+00 TO 59+50	244	INLET TO INLET
67+50	38	ACROSS 19TH ST
LT 67+50 TO 69+18.69	186	MANHOLE TO MANHOLE
PROJECT TOTAL	964	

550A0090

STORM SEWER REMOVAL 12"		
STATION	FOOT	REMARKS
RT 51+74.64 TO 51+97.63	23	
LT 51+89.51 TO 51+97.73	15	
RT 51+95.67 TO 51+97.68	6	
LT & RT 51+97.68	33	ACROSS ROAD
LT 64+57.60 TO RT 64+62.19	38	ACROSS ROAD
LT 64+57.60 TO 69+18.69	460	
LT & RT 67+17.73	36	ACROSS ROAD
RT 67+17.73	5	
RT 68+88.51 TO LT 68+92.06	43	ACROSS ROAD
RT 68+88.51 TO 69+08.60	28	BENEATH SIDEWALK
PROJECT TOTAL	687	

55100500*

MANHOLES, TYPE A, 4' - DIAMETER, TYPE 1 FRAME, CLOSED LID		
STATION	EACH	REMARKS
25.08' RT 67+17.73	1	RECONNECT EXIST. STORM SEWER (SOUTH SIDE)
17.5' LT 67+50	1	
PROJECT TOTAL	2	

60218400

INLETS, SPECIAL, NO. 5		
STATION	EACH	REMARKS
LT 53+50	1	
RT 53+50	1	
LT 57+00	1	
RT 57+00	1	
LT 59+50	1	
RT 59+50	1	
LT 64+50	1	
RT 64+50	1	
RT 65+28.28	1	
LT 67+50	1	
RT 67+50	1	
PROJECT TOTAL	11	

60242801*

MANHOLES TO BE ADJUSTED		
STATION	EACH	REMARKS
26.71' RT 51+74.64	1	STORM SEWER
8.36' RT 53+84.85	1	SANITARY SEWER
5.81' RT 56+14.65	1	SANITARY SEWER
PROJECT TOTAL	3	

60255500

VALVE BOXES TO BE ADJUSTED		
STATION	EACH	REMARKS
RT 52+10.35	1	WATER
LT 56+35.01	1	WATER
LT 57+04.33	1	WATER
LT 64+72.22	1	WATER
LT 64+76.24	1	WATER
LT 65+22.52	1	WATER
RT 66+83.50	1	WATER
PROJECT TOTAL	7	

60266600

REMOVING MANHOLES		
STATION	EACH	REMARKS
31.41' LT 51+89.51	1	
25.27' RT 51+95.66	1	
17' LT 64+57.60	1	
23' RT 64+62.19	1	
PROJECT TOTAL	4	

60500040

REMOVING INLETS		
STATION	EACH	REMARKS
17' LT 51+97.73	1	
18' RT 51+97.63	1	
19' RT 67+17.76	1	
19' RT 68+88.51	1	
24.5' LT 68+92.06	1	
PROJECT TOTAL	5	

60500060

COMBINATION CONCRETE CURB & GUTTER, TYPE B - 6.18		
STATION	FOOT	REMARKS
LT 51+73.96 TO 51+91.04	25	RADIUS
LT 51+91.04 TO 68+90.02	1,699	
LT 68+90.02 TO 69+12.10	33	RADIUS
RT 51+73.41 TO 51+95.49	33	RADIUS
RT 51+95.49 TO 56+24.13	429	
RT 56+24.13 TO 56+46.21	33	RADIUS
RT 56+73.05 TO 56+95.13	33	RADIUS
RT 56+95.13 TO 64+53.19	758	
RT 64+53.19 TO 64+75.27	33	RADIUS
RT 65+07.78 TO 65+25.27	55	RADIUS
RT 65+25.27 TO 68+92.74	367	
RT 68+92.74 TO 69+09.81	26	RADIUS
PROJECT TOTAL	3,525	

60604400

STORM SEWERS, SPECIAL 12"		
STATION	FOOT	REMARKS
53+50	46	ACROSS 19TH ST
57+00	46	ACROSS 19TH ST
RT 64+50 TO 65+28.28	74	ACROSS 9TH AVE
PROJECT TOTAL	166	

61140200*

PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS		
STATION	SO FT	REMARKS
RT 64+40	11.8	STOP - (6' LETTERS)
LT 65+27	11.8	STOP - (6' LETTERS)
PROJECT TOTAL	23.6	

78001100

PAINT PAVEMENT MARKING - LINE 4"		
STATION	FOOT	REMARKS
LT 51+84 TO 52+35	95	LANE LINES AND DIAGONALS
LT 52+35 TO 64+35	470	PARKING STALL LINES
LT 64+35 TO 65+71	241	LANE LINES AND DIAGONALS
LT 65+71 TO 68+46	100	PARKING STALL LINES
LT 68+46 TO 69+01	107	LANE LINES AND DIAGONALS
RT 51+84 TO 52+23	81	LANE LINES AND DIAGONALS
RT 52+23 TO 55+85	100	PARKING STALL LINES
RT 55+85 TO 56+43	110	LANE LINES AND DIAGONALS
RT 56+76 TO 57+35	107	LANE LINES AND DIAGONALS
RT 57+35 TO 64+10	260	PARKING STALL LINES
RT 64+10 TO 64+72	115	LANE LINES AND DIAGONALS
PROJECT TOTAL	2,094	

78001110

PAINT PAVEMENT MARKING - LINE 4" CONTINUED		
STATION	SO FT	REMARKS
RT 65+16 TO 65+46	63	LANE LINES AND DIAGONALS
RT 65+46 TO 68+46	100	PARKING STALL LINES
RT 68+46 TO 69+01	145	LANE LINES AND DIAGONALS
PROJECT TOTAL	2,094	

78001110

PAINT PAVEMENT MARKING - LINE 6"		
STATION	SO FT	REMARKS
51+79 TO 51+84	109	CROSSWALK LINES
RT 56+41 TO 56+78	69	CROSSWALK LINES
64+71 TO 65+16	166	CROSSWALK LINES
69+01 TO 69+06	108	CROSSWALK LINES
PROJECT TOTAL	452	

78001130

PAINT PAVEMENT MARKING - LINE 12"		
STATION	FOOT	REMARKS
51+79 TO 51+84	69	DIAGONALS IN CROSSWALK
RT 56+41 TO 56+78	46	DIAGONALS IN CROSSWALK
64+71 TO 65+16	104	DIAGONALS IN CROSSWALK
69+01 TO 69+06	66	DIAGONALS IN CROSSWALK
PROJECT TOTAL	285	

78001150

PAINT PAVEMENT MARKING - LINE 24"		
STATION	FOOT	REMARKS
LT 51+88	18	STOP BAR
RT 56+59.60	14	STOP BAR
RT 64+45	12	STOP BAR
RT 64+94	12	STOP BAR
LT 65+20	12	STOP BAR
RT 68+95	13	STOP BAR
PROJECT TOTAL	81	

78001180

SHORT-TERM PAVEMENT MARKING		
STATION	FOOT	REMARKS
51+70.70 TO 69+14.64	176	36' SPACING FROM END TO END
PROJECT TOTAL	176	

70300100*

BREAKER-RUN CRUSHED STONE		
STATION	TON	REMARKS
CONTINGENCY ITEM	615	AS DIRECTED BY THE ENGINEER
PROJECT TOTAL	615	

70005400*