

# SUMMARY OF QUANTITIES

SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
05-00012-00-FP	HENRY	75	3
STA.		TO STA.	
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT	

CODE NUMBER	PAY ITEMS	UNIT	QUANTITIES				
			TOTAL QUANTITY	HP ELIGIBLE J000 P. C. CONCRETE	ITEP ELIGIBLE J000 P. C. CONCRETE	FED HP GRANT ELIGIBLE Y080	NON PARTICIPATING
20200100	EARTH EXCAVATION	C. Y.	2,760.0	2,760			
20800150	TRENCH BACKFILL	C. Y.	1,749	1,749			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	80	80			
28000400	PERIMETER EROSION BARRIER	FT.	445	445			
28000500	INLET AND PIPE PROTECTION	EACH	17	17			
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	6,377	6,377			
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	107	107			
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	50	50			
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	54	54			
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	64	64			
42000301	PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)	S. Y.	7,922	7,922			
42001300	PROTECTIVE COAT	S. Y.	7,922	7,922			
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	S. Y.	207	207			
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	S. F.	18,840	5,501	13,339		
42400800	DETECTABLE WARNINGS	S. F.	64	64			
44000100	PAVEMENT REMOVAL	S. Y.	10,180	10,180			
44000200	DRIVEWAY PAVEMENT REMOVAL	S. Y.	147	147			
44000600	SIDEWALK REMOVAL	S. F.	16,074	4,313	11,761		
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	S. Y.	163	163			

\*SPECIALTY ITEMS