

**SUMMARY OF QUANTITIES CON'T.**

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
C.H. 14 F.A.S. 209	00-00091-00-BR	MERCER	111	3
FED. ROAD DIST. NO.	ILLINOIS PROJECT			

CONTRACT NO. 89312

ITEM	DESCRIPTION	UNIT	TOTAL QUANTITY	HPP FUNDS	NATIONAL CORRIDOR PLANNING FUNDS	HBP FUNDS
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	244		244	
542A1060	PIPE CULVERTS, CLASS A, TYPE 2 15"	FOOT	188		188	
542A1063	PIPE CULVERTS, CLASS A, TYPE 2 18"	FOOT	86		86	
542A1069	PIPE CULVERTS, CLASS A, TYPE 2 24"	FOOT	64		64	
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	126		126	
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	2		2	
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	6		6	
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	194			194
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	524			524
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1		1	
60258000	MANHOLES TO BE RECONSTRUCTED (SPECIAL)	EACH	1		1	
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4		4	
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4		4	
63200305	STEEL PLATE BEAM GUARD RAIL REMOVAL	FOOT	304		304	
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	6	6		
66700205	PERMANENT SURVEY MARKERS, TYPE 1	EACH	9		9	
67100100	MOBILIZATION	L SUM	1		1	
70100450	TRAFFIC CONTROL AND PROTECTION STANDARD 701201	L SUM	1		1	
70100460	TRAFFIC CONTROL AND PROTECTION STANDARD 701306	L SUM	1		1	
70103700	TRAFFIC CONTROL COMPLETE	L SUM	1		1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	20		20	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	23400		23400	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	28016		28016	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3650		3650	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	19716		19716	
* 78200400	GUARDRAIL REFLECTORS	EACH	8	8		
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4		4	

ITEM	DESCRIPTION	UNIT	TOTAL QUANTITY	HPP FUNDS	NATIONAL CORRIDOR PLANNING FUNDS	HBP FUNDS
* A2002912	TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), 1 1/2" CALIPER, BALLED AND BURLAPPED	EACH	9		9	
* A2004212	TREE, FRAXINUS PENNSYLVANICA SUMMIT (SUMMIT GREEN ASH), 1 1/2" CALIPER, BALLED AND BURLAPPED	EACH	9		9	
* A2005114	TREE, JUGLANS NIGRA (BLACK WALNUT), 1 3/4" CALIPER, BALLED AND BURLAPPED	EACH	9		9	
* A2006512	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 1 1/2" CALIPER, BALLED AND BURLAPPED	EACH	9		9	
* A2006912	TREE, QUERCUS PALUSTRIS (PIN OAK), 1 1/2" CALIPER, BALLED AND BURLAPPED	EACH	9		9	
* X0321116	WETLAND SEEDING (SPECIAL)	ACRE	0.52		0.52	
X2111100	TOPSOIL EXCAVATION AND PLACEMENT, SPECIAL	CU YD	623		623	
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	9		9	
X4023000	TEMPORARY ACCESS (ROAD)	EACH	1		1	
XX004096	REMOVE AND RE-INSTALL CONCRETE FLARED END SECTIONS	EACH	1	1		
XX004829	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12", SPECIAL	EACH	1		1	

\* SPECIALTY ITEMS

SUMMARY OF QUANTITIES		
Date	Designed: RLS	F.A.S. 209 (C.H. 14) OVER KEATING CREEK NEW BOSTON ROAD SECTION 00-00091-00-BR MERCER COUNTY
Revisions	Drawn: RLS	
	Checked: SMK	
	Approved: SMK	
Prepared by:	<b>URS</b>	345 East Ash Avenue Decatur, IL 62526
		URS Job No. 21-00001253.01