

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8183	04-00120-00-FP	MORGAN	28	3
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	36
20200100	EARTH EXCAVATION	CU YD	3,815
20800150	TRENCH BACKFILL	CU YD	513
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	35
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	35
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	35
25200100	SODDING	SQ YD	2,781
25200200	SUPPLEMENTAL WATERING	UNIT	25
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	58
28000300	TEMPORARY DITCH CHECKS	EACH	3
28000400	PERIMETER EROSION BARRIER	FOOT	250
28000500	INLET AND PIPE PROTECTION	EACH	19
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	7,039
35101400	AGGREGATE BASE COURSE, TYPE B	TON	93
35501312	HOT-MIX ASPHALT BASE COURSE, 7"	SQ YD	6,040
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	14
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	149
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	1,299
40600300	AGGREGATE (PRIME COAT)	TON	13
40600895	CONSTRUCTING TEST STRIP	EACH	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	352
40600990	TEMPORARY RAMP	SQ YD	54
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	846
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D" N50	TON	537
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	23
42001300	PROTECTIVE COAT	SQ YD	2,901
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	112
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	126
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	14,046
42400800	DETECTABLE WARNINGS	SQ FT	50
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	123
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	324
44000600	SIDEWALK REMOVAL	SQ FT	1,977
50105220	PIPE CULVERT REMOVAL	FOOT	272
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1
55100500	STORM SEWER REMOVAL 12"	FOOT	66
55101200	STORM SEWER REMOVAL 24"	FOOT	100
56106300	ADJUSTING WATER MAIN 6"	FOOT	175
56300100	ADJUSTING SANITARY SEWERS, 8 INCH DIAMETER OR LESS	FOOT	320

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
Δ • 56300300	ADJUSTING WATER SERVICE LINES	FOOT	260
Δ • 56400100	FIRE HYDRANTS TO BE MOVED	EACH	2
Δ • 56500200	DOMESTIC WATER SERVICE BOXES TO BE MOVED	EACH	6
Δ • 56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	2
• 60218500	MANHOLES, TYPE A, 4"-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	5
• 60221200	MANHOLES, TYPE A, 5"-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	3
• 60235300	INLETS, TYPE A, TYPE 1 FRAME, CLOSED LID	EACH	1
• 60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	2
• 60238305	INLETS, TYPE A, WITH MEDIAN INLET (604101)	EACH	3
• 60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	4
• 60240366	INLETS, TYPE B, WITH MEDIAN INLET (604106)	EACH	1
• 60255500	MANHOLES TO BE ADJUSTED	EACH	6
• 60266600	VALVE BOXES TO BE ADJUSTED	EACH	2
• 60500060	REMOVING INLETS	EACH	2
• 60600505	CONCRETE CURB (SPECIAL)	FOOT	69
• 60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	3,263
• 67100100	MOBILIZATION	L SUM	1
• 70103700	TRAFFIC CONTROL COMPLETE	L SUM	1
• 70300100	SHORT-TERM PAVEMENT MARKING	FOOT	532
• 70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	188
• 70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	3,526
• 70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	315
• 70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	69
• 70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2,052
Δ 78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	3,526
Δ 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	315
Δ 78004200	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LETTERS AND SYMBOLS	SQ FT	188
Δ 78004280	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 24"	FOOT	69
• X0322033	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	914
• X0322034	STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH	FOOT	222
• X0322035	STORM SEWER (WATER MAIN REQUIREMENTS) 18 INCH	FOOT	378
• X0322125	STORM SEWER (WATER MAIN REQUIREMENTS) 24 INCH	FOOT	386
• XX000856	MAILBOX REMOVAL AND RELOCATION	EACH	8
• Z0013798	CONSTRUCTION LAYOUT	L SUM	1

• SEE SPECIAL PROVISIONS
 Δ SPECIALTY ITEMS

NOTE: ALL ITEMS ARE UNDER CONSTRUCTION TYPE CODE 1000

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

LINCOLN AVENUE
SUMMARY OF QUANTITIES

DATE JULY, 2006

DRAWN BY JCW
CHECKED BY JRB